TECHNICAL PUBLICATION EMA #388

Water Budget Analysis for the Everglades Nutrient Removal Project and Stormwater Treatment Area 1 West (August 20, 1998 to June 30, 2000)

December 2000

by

Wossenu Abtew, John H. Raymond & Muluneh Imru

Hydro Information Systems & Assessment Department Environmental Monitoring & Assessment Division South Florida Water Management District 3301 Gun Club Road West Palm Beach, Florida 33406

EXECUTIVE SUMMARY

The Everglades Nutrient Removal Project (ENR) is a 1,544 hectare (ha) or 3,815 acre (ac) constructed wetland, designed and operated for the demonstration of phosphorus (P) reduction from agricultural runoff/drainage. The ENR is located in south Florida (26° 38 N, 80° 25 W) at the eastern edge of the Everglades Agricultural Area (EAA). The EAA is a 240,000 ha (593,000 ac) highly productive irrigation/drainage basin with a major production of sugarcane. Ecological changes in the Everglades have been partially attributed to an increase in phosphorus (P) concentration in the inflow waters. Local, state and federal initiatives have been taken to reduce P associated with agricultural runoff/drainage. The ENR is an example of one of these initiatives and is a field scale prototype for a larger scale Stormwater Treatment Area (STA). It was operated for close to five years and became part of the larger constructed wetland, Stormwater Treatment Area 1 West (STA-1W). The total area of STA-1W is 2,772 ha (6,849 ac) with Cell 5, the northerm expansion of ENR, covering 1,228 ha (3,034 ac).

This report has two sections. Section I presents water budget analysis for the ENR covering the last months of the project before it started fully operating as part of STA-1W (August 20, 1998 to June 30, 1999). Section II of this report presents the first year water budget for STA-1W (July 1, 1999 to June 30, 2000).

The total inflow to the ENR through the inflow pump for the 315-day study period was 7,620 hectare-meters (ha-m) or 61,774 acre-feet (ac-ft) and the total outflow through the outflow pump was 7,768 ha-m (62,974 ac-ft). Estimated seepage inflow from the L-7 levee through the roadside culverts was a total of 426 ha-m (3,453 ac-ft). The seepage recirculation pump had a total flow of 2,519 ha-m (20,421 ac-ft). Total areal average rainfall for the study period was 115.2 centimeters (cm) or 45.4 inches (in) and the total areal average evapotranspiration was 108.6 cm (42.8 in). The mean hydraulic loading rate for the study period, based on the G-250 pump inflow, was 1.57 centimeters per day (cm d⁻¹) or 0.62 inches per day (in d⁻¹). The mean-estimated volume was computed from the area-weighted (by cell) mean depth of 48.7cm (19.2 in) and total area of 1,544 ha (3,815 ac). The estimated mean hydraulic retention time was 30.5 days.

STA-1W has been in operation for one year but the main outflow structure pump station G-310 has been under construction. For the period of analysis, the total inflow through the spillway was 14,636 ha-m or 118,651 ac-ft and the total outflow through the pump was 14,977 ha-m (121,416 ac-ft). Estimated seepage inflow from the L-7 levee through the roadside culverts was a total of 438 ha-m (3,551 ac-ft). The seepage and recirculation pump had a total flow of 6,688 ha-m (54,218 ac-ft). Total areal average rainfall for the study period was 100.8 cm (39.7 inches) and the total areal average evapotranspiration was 137.6 cm (54.2 inches). The sum of the errors and unknowns, was 1.1 percent of the inflows to the system. The mean hydraulic loading rate for the one-year period, based on the G-302 inflow, was 1.45 cm d⁻¹ (0.57 in d⁻¹). The mean-estimated volume was computed from the area-weighted (by cell) mean depth of 51.9 cm (20.4 inches) and total area of 2,772 ha (6,849 ac). The estimated mean hydraulic retention time was 35.2 days.

. .

.

. .

. .

TABLE OF CONTENTS

EXECUTIVE SUMMARY
TABLE OF CONTENTS
LISTOF FIGURES iv
LIST OF TABLES
LIST OF ABBREVIATIONS AND ACRONYMS
CONVERSION FACTORS
ACKNOWLEDGEMENTS vii
INTRODUCTION
SECTION I. EVERGLADES NUTRIENT REMOVAL PROJECT (ENR)
Site Description
ENR SYSTEM HYDRAULICS AND OPERATION 2
System Hydraulics
ENR HYDROLOGY AND HYDROLOGIC MONITORING
Rainfall 7 Evapotranspiration 10 Flows 10 Water Levels 13
ENR WATER BUDGET COMPUTATIONS 15
ENR Water Balance Model
ENR WATER BUDGET SUMMARY 21

SECTION II. STORMWATER TREATMENT AREA 1 WEST (STA-1W)	22
Site Description	22
Vegetation Cover and Monitoring	22
STA-1W SYSTEM HYDRAULICS AND OPERATION	22
System Hydraulics	22
Operation	27
Transitional Operation of Cell 5	27
STA-1W HYDROLOGY AND HYDROLOGIC MONITORING	28
Rainfall	28
Evapotranspiration	28
Flows	31
Water Levels	31
STA-1W WATER BUDGET COMPUTATIONS	36
STA-1W Water Balance Model	36
Discussion	38
STA-1W WATER BUDGET SUMMARY	39
REFERENCES	41
APPENDIX I: ENR Water Balance Terms With Calculated Remainders	43
APPENDIX II: STA-1W Cell 5 Average	51
APPENDIX III: STA-1W Water Balance Terms With Calculated Remainders	55

.

•

•

. ,

LIST OF FIGURES

Figure 1	Location of the Everglades Nutrient Removal Project	
2	and Stormwater Treatment Area 1 West.	2
Figure 2.	ENR structures and monitoring network	4
Figure 3.	Daily distribution of areal average rainfall and evapotranspiration in the ENR	8
Figure 4.	Daily pumping rates of inflow and outflow pumps in ENR	12
Figure 5.	Daily pumping rates of the seepage pump and seepage flow	
8	through L-7 levee roadside seepage collection culverts in ENR	12
Figure 6.	Daily mean water levels in the eastern cells of the ENR and the Buffer Cell	14
Figure 7.	Daily mean water levels in the western cells of the ENR and the Buffer Cell	14
Figure 8	Schematic hydrologic model for the ENR	16
Figure 9.	Distribution of daily remainders (errors and unknowns)	
	from the ENR water balance	18
Figure 10.	STA-1W structures and monitoring network	26
Figure 11.	Daily distribution of areal average rainfall and evapotranspiration in STA-1W	29
Figure 12.	Daily STA-1W inflows and outflows	33
Figure 13.	Daily pumping rates of the seepage/recirculation pump and seepage flow	
	through L-7 levec roadside seepage collection culverts in STA-1W.	33
Figure 14.	Daily mean water levels in Cells 1 and 3 of STA-1W	34
Figure 15.	Daily mean water levels in Cells 2 and 4 of STA-1W	35
Figure 16.	Daily mean water levels in Cell 5 of STA-1W	35
Figure 17.	Schematic hydrologic model for STA-1W	37
Figure 18	Distribution of daily remainders (errors and unknowns)	
6ui 0 10.	from STA-1W water balance	39

.

LIST OF TABLES

Table 1.	Site characteristics of the Everglades Nutrient Removal Project	5
Table 2.	Rainfall stations in the ENR, database retrieval keys and Thiessen weights	7
Table 3.	ENR Project monthly flows, areal weighted rainfall and ET	
	(August 20, 1998 to June 30, 1999).	9
Table 4.	Flow control structures, stage recorders and database retrieval keys	
	used in the water budget analysis of the ENR.	. 11
Table 5.	Observed water surface elevations and depths in the ENR	
	(August 20, 1998 to June 30, 1999)	.13
Table 6.	Summary of the water budget of the ENR (August 20, 1998 to June 30, 1999)	. 1 9 ·
Table 7.	Comparison of ENR water budget (1998-1999) components	
	with the previous four years	. 20
Table 8.	Site characteristics of Stormwater Treatment Area 1 West	.23
Table 9.	Structure information for STA-1W stations	.25
Table 10.	Rainfall stations in STA-1W, database retrieval keys and Thiessen weights	.28
Table 11.	STA-1W monthly flows, areal weighted rainfall and ET	
	(July 1, 1999 to June 30, 2000)	.30
Table 12.	Flow control structures, stage recorders and database retrieval keys	
	used in the water budget analysis for STA-IW.	.32
Table 13.	Observed water surface elevations and depths in STA-1W	
	(July 1, 1999 to June 30, 2000)	.34
Table 14.	Summary of water budget for STA-1W (July 1. 1999 to June 30, 2000)	.40

.

.

LIST OF ABBREVIATIONS AND ACRONYMS

ac	acre
ac-ft	acre-foot
BMP	Best Management Practices
cm	centimeter
cm d ⁻¹	centimeter per day
cfs	cubic foot per second
EAA	Everglades Agricultural Area
ENR	Everglades Nutrient Removal
ÉT	Evapotranspiration
ft	foot
ha	hectare
ha-m	hectare-meter
HW	Headwater
in	inch
in d ⁻¹	inch per day
m	meter
$m^{3}s^{-1}$	cubic meter per second
MAX	Maximum
mm	millimeter
MIN	Minimum
NGVD	National Geodetic Vertical Datum
Р	Phosphorus
Q	Discharge
rpm	Rotation per minute
SFWMD	South Florida Water Management District
STA	Stormwater Treatment Area
TW	Tailwater
UVM	Ultrasonic Velocity meter
WCA	Water Conservation Area

CONVERSION FACTORS

METRIC

ENGLISH

mm	0.03937 in
cm	0.3937 in
m	3.2808 ft
ha	2.47 ac
$m^{3}s^{-1}$	35.33 cfs
ha-m	8.1068 ac-ft

ACKNOWLEDGEMENTS

The authors would like to acknowledge the following District staff for reviewing the drafts of the report: Scott Huebner, Nagendra Khanal, Garth Redfield, Zaki Moustafa, Jana Newman and Martha Nungesser.

INTRODUCTION

Background

The Everglades Nutrient Removal (ENR) Project is a 1,544 hectare (ha) or 3,815 acre (ac) constructed wetland, designed and operated to demonstrate the feasibility of large-scale phosphorus reduction from agricultural runoff/drainage. The project is located in South Florida (26° 38' N, 80° 25' W) at the eastern edge of the Everglades Agricultural Area (Figure 1). The Everglades Agricultural Area (EAA) is a 240,000 ha (593,000 ac) highly productive irrigation/drainage basin with a major production of sugarcane. Ecological changes in the Everglades have been partially attributed to an increase in phosphorus (P) concentrations in the inflow waters. Local, state and federal initiatives have been taken to reduce total phosphorous load from agricultural runoff/drainage from the agricultural area flows to the south and southeast through four primary canals shown in Figure 1 (Miami, North New River, Hillsboro, West Palm Beach).

A minimum of 25 percent of the total phosphorous load in agricultural runoff/drainage is required to be removed at the farm level through the application of various agricultural Best Management Practices (Whalen and Whalen, 1994). Further removal of P is to be achieved through constructed wetland treatment systems known as Stormwater Treatment Areas (STAs). The ENR is a field scale prototype for the large scale STAs. It is built on farmland owned by the State of Florida and previously leased (until 1988) to Knight's Farm for sugarcane and corn production. Originally, the land was part of the Everglades which consisted of wetland prairies, sloughs and stands of custard apple (Davis, 1943). Construction of the ENR started in August 1992 and was completed in October 1993. The inflow and outflow pumps started operation in August 1994. The ENR was operated for close to five years before becoming part of Stormwater Treatment Area 1 West (STA-1W) at the beginning of July 1999.

Stormwater Treatment Area 1 West is a larger scale constructed wetland, which incorporates the ENR and has a total area of 2,772 hectares (6,849 acres). The ENR was expanded to the north with the addition of Cell 5 (1,228 hectares, 3034 acres) to form STA-1W. The total average design flow volume is 17,621 ha-m (142,853 ac-ft) (SFWMD, 1998). Construction was completed and discharge into Cell 5 started in February of 1999. The ENR was run concurrently until end of June of 1999.

This report has two sections. Section I presents water budget analysis for the ENR covering the last months of the project before it started fully operating as part of STA-1W (August 20, 1998 to June 30, 1999). Water budget analyses for the previous four years of the ENR project (August 19, 1994 to August 19, 1996; August 20, 1996 to August 19, 1997; August 20, 1997 to August 19, 1998) were reported in three South Florida Water Management District Technical Memorandums (SFWMD, 1996; Abtew and Mullen, 1997; Abtew and Downey, 1998). Section II of this report presents the first year water budget for STA-1W (July 1, 1999 to June 30, 2000).



Figure 1. Location of the Everglades Nutrient Removal Project and Stormwater Treatment Area 1 West

SECTION I

EVERGLADES NUTRIENT REMOVAL PROJECT (ENR)

Site Description

The ENR Project area is primarily covered by Okeechobee muck soils with very small topographic relief and an average ground elevation of 3 meters (m) or 9.84 feet (ft) NGVD; a 1 to 2 m layer of peat overlies on several meters of carbonate rock (Jammal and Associates, Inc., 1991). To the east, the L-7 levee separates the ENR Project from the Loxahatchee Wildlife Refuge (Water Conservation Area 1, WCA1). The northern and western sides of the ENR are encompassed by a seepage canal that separates the ENR levee from agricultural fields. The narrow, southern ENR levee runs along Knight's Farm, which currently is not under cultivation. A 12-km (7.5-mile) levee surrounds the ENR and internal levees separate the five interior cells. The Project consists of two parallel treatment trains of two cells each and a buffer (distribution cell). As shown in Figure 2, the upper two cells, Cells 1 and 2, are treatment cells. The lower two cells, Cells 3 and 4, are polishing cells. The eastern treatment train carries water from the Buffer Cell to Cell 1, then to Cell 3 and finally to the outflow pump. The western treatment train carries water from the ENR has been incorporated into STA-1W, which comprises five cells: Cells 1, 2, 3, 4 and 5. Average ground elevation and area for each cell is shown in Table 1.

Vegetation Cover and Monitoring

As part of the ENR monitoring plan, temporal and spatial changes of vegetation have been documented using quarterly aerial photography prior to 1995 and semi-annually since 1995. Average vegetation cover for the Buffer Cell and Cells 1, 2, 3, and 4 of the ENR, estimated from an aerial photograph of November 6, 1998 and April 13, 1999 is shown in **Table 1**. The dominant covers are cattail (37%), open water/submerged aquatics (31%), followed by mixed vegetation (19%), algae/macrophyte complex (7%) and floating aquatics (6%).

ENR SYSTEM HYDRAULICS AND OPERATION

System Hydraulics

West Palm Beach canal water that would otherwise be pumped into the Loxahatchee Wildlife Refuge or WCA1 via the S5-A Pump Station was partially diverted to the ENR through five culverts and a 3.4 km (2.1 mile) supply canal. Inflow into the constructed wetland, outflow from the constructed wetland, and seepage recycling are performed with lift pumps. The inflow pump station (G-250) had six identical pumps with a total capacity of 16.98 cubic meters per second ($m^3 s^{-1}$) or 600 cubic feet per second (cfs). The inflow pumps lifted water from the delivery canal into the Buffer Cell. The outflow pump station (G-251) had six identical pumps with a total capacity of 12.74 m³ s⁻¹ (450 cfs). The outflow pumps lifted treated effluent from the ENR into the Loxahatchee Wildlife Refuge.



Figure 2. ENR structures and monitoring network

Table 1. Site characteristics of the Everglades Nutrient Removal Project.

Cell	Area	Average Ground Elev			Land Cover*		
	ha (ac)	m (ft) NGVD	Cattails (%)	Algae/Macrophyte complex (%)	Floating aquatics (%)	Mixed veg. (%)	Open water/ Submerged aquatics (%)
Buffer	55 (136)	3.10 (10.17)	4	0	43	8	2
Cell I	525 (1297)	3.13 (10.25)	30	0	ŝ	21	44
Cell 2	414 (1023)	2.94 (9.65)	46	0	6	Т	44
Cell 3	404 (998)	3.10 (10.18)	47	0	1	41	11
Cell 4	146 (361)	3.00 (9.83)	v	79	0	1	15
Total	1544 (3815)	3.02 (9.92)*	37	7	9	19	31

* average land cover for ENR (based on November 6, 1998 and April 13, 1999 observations). # area-weighted average ground elevation.

Ś

Seepage from the seepage canal was pumped into the Buffer Cell by three identical pumps (G-250S) with a total capacity of 5.66 m³ s⁻¹ (200 cfs). Water surface elevation was monitored by automated stage recorders, and staff gages supplemented stage readings for operation.

As part of the incorporation of the ENR into the larger STA-1W, there were changes to the ENR hydraulic structures and their functions. The old ENR seepage canal was plugged at the end of February 1999 and G-250S quit pumping ENR seepage, as was the case in the previous four years of its operation. The sheet pile that separated the ENR seepage canal from the ENR supply canal was removed in the middle of March 1999. Between March 1999 and the beginning of July 1999, G-250S was used as the main inflow pump to the ENR. Later, three of the pump units from G-250 (original ENR inflow pump) were removed and three pump units remained to supplement G-250S in emergency conditions. Since July 1999, the function of G-250S is to pump seepage from Cell 5 of STA-1W into Cell 1. The current total capacity of the three main pumps is 5.66 m³ s⁻¹ (200cfs) and the three supplemental pumps have total capacity of 8.49 m³ s⁻¹ (300 cfs) for a combined capacity of 14.15 m³ s⁻¹ (500 cfs).

Inter-cell flows are regulated with risers through 16.7 m (55 ft) long and 1.83 m (6 ft) diameter culverts. In the eastern treatment train, water flowed from the Buffer Cell into Cell 1 through ten culverts (G-252A-J) until the beginning of March, 1999 when the seven western side culverts (A through G) were removed and the levee degraded. Water flows from Cell 1 to Cell 3 through ten culverts (G-253A-J). Water from Cell 3 is directed to the outflow pump through collection canals. In the western treatment train, water flowed from the Buffer Cell into Cell 2 through five culverts (G-255A-E) but later two additional 72 inches culverts were added on the southern side as part of STA-1W construction. Water flowed from Cell 2 to Cell 4 through five culverts (G-254A-E) but later four more culverts were added as part of STA-1W construction and naming changed to G-254A, A1, B, B1, C, C1, D, D1 and E. Outflow from Cell 4 moves through five culverts (G-256A-E) into a discharge canal that leads to the outflow pump. Water can be recirculated from Cell 2 and Cell 4 via the seepage canal by being released through culverts (G-258 and G-259, respectively) in the western levce. Water can be transferred from Cell 1 to Cell 4 through culvert G-257 when necessary. Flow through culverts is being monitored with UVMs. ENR structure locations and monitoring network are shown in Figure 2. Other hydraulic changes associated with STA-1W construction are presented in Section II.

Operation

Guardo and Kosier (1993) developed a preliminary operation plan for the ENR. Early and late startup water depths and stages were recommended. The seepage pump started operation in December 1993. Pumping was mainly to recirculate water from the seepage canal and reroute water from cell to cell. The inflow and outflow pumps started operating on August 19, 1994, marking the beginning of full-scale operation of the ENR. Inflow and outflow regulations have been a result of many conditions, such as the stage in each cell, S-5A pump station status, seepage tests, construction operations, pump maintenance and others. Through the five years of operation the mean depth in the Buffer Cell, Cells 1, 2, 3 and 4 was 60 cm (24 in), 50 cm (20 in), 71 cm (28 in), 36 cm (14 in) and 59 cm (23 in), respectively.

ENR HYDROLOGY AND HYDROLOGIC MONITORING

Rainfall

South Florida has a subtropical climate with relatively high rainfall frequency of occurrence and magnitude. On the average, 34% of the annual rainfall occurs in the dry season (November to May), with the remaining 66% occurring in the wet season (June to October). Mean annual rainfall for the area is 133 centimeters (cm) or 52 inches (in) as reported in Abtew and Khanal (1994). Frontal rainfalls occur in the dry season and have relatively lower spatial variation. Rainfall during the wet season is associated with daily convective and tropical systems, which have high spatial variations.

Based on the high variation of summer rainfall observations in the area, a ten-gage rainfall network was established as a pilot network to evaluate the optimum gage density needed for the project area. Network analysis of the first wet season daily rainfall showed that five gages were sufficient for the area (Abtew et al., 1995). As a result, three gages were removed. However, a seven-gage network is maintained because two of the gages are associated with two weather stations, and four gages (one at the middle of each cell) are part of the monitoring network required by the operating permit. On March 4, 1999, station ENR105 was discontinued and currently, there are six raingages. Table 2 lists all the rainfall gaging stations, the corresponding database keys and respective Thiessen weights. Figure 2 shows the gage locations. Areal average rainfall on the project site was computed as a Thiessen-weighted average of the stations. Stations with few instances of data gaps were estimated from the closest gage. The daily distribution of areal average rainfall for the study (August 20, 1998 to June 30, 1999) is depicted by Figure 3. Monthly summary of areal average rainfall for the ENR is shown in Table 3. The total areal average rainfall for ENR (August 20, 1998 to June 30, 1999) was 115.2 cm (45.4 in).

Stations	DBKEY	Thiessen	Weights	
ENR101	15851	0.160	0.087	
ENR105	15861	0.143		
ENR106	DU515	0.107	0.441	
ENR203	15874	0.183	0.222	
ENR301	15877	0.224	0.126	
ENR308	15888	0.072	0.049	
ENR401	15862	0.111	0.075	

Table 2. Rainfall stations in the ENR, database retrieval keys and Thiessen weights.



Daily Evapotranspiration (mm)

Figure 3. Daily distribution of areal average rainfall and evapotranspiration in the ENR

Table	3. ENR Project mc	onthly flows,	areal weighted rai	infall and ET (A	ugust 20, 1998 to Ji	une 30, 1999).	
Ycar	Month	Inflow	Outflow	Rainfall	ET	Seepage pump	Seepage L-7
		G-250	G-251			G-250_S	culverts
		ha-m	ha-m	cm (in)	cm (in)	ha-m	ha-m
1998	Aug*	98	219	4.75 (1.87)	5.80 (2.28)	141	8
1998	Sept	667	725	28.63 (11.27)	10.68 (4.20)	426	50
1998	Oct	1451	859	5.51 (2.17)	11.42 (4.50)	485	55
1998	Nov	707	1358	20.88 (8.22)	8.92 (3.51)	478	103
1998	Dec	558	707	6.10 (2.40)	7.67 (3.02)	395	74
1999	Jan	847	817	5.69 (2.24)	7.57 (2.98)	406	55
1999	Feb	569	701	1.45 (0.57)	7.85 (3.09)	188	33
1999	Mar	276	141	1.65 (0.65)	11.61 (4.57)	0	12
1999	Apr	1252	74]	2.95 (1.16)	12.89 (5.07)	0	0
1999	May	659	630	6.76 (2.66)	13.73 (5.41)	0	0
1999	June	536	870	30.81 (12.13)	10.49 (4.13)	0	36

* 12 days

Evapotranspiration

Daily evapotranspiration is computed from high resolution weather data using a radiation-based evapotranspiration estimation model developed from lysimeter studies in the ENR (Abtew, 1996a, 1996b). A complete weather station was located in Cell 1 (ENR105) and another is located in Cell 3 (ENR308). Currently, ENR308 is the only weather station operational as ENR105 was discontinued in early 1999. The daily distribution of evapotranspiration for the ENR for the study period (August 20, 1998 to June 30, 1999) is depicted by Figure 3. Monthly summary of evapotranspiration for the ENR is shown in Table 3. The total evapotranspiration for ENR (August 20, 1998 to June 30, 1999) was 108.6 cm (42.8 in).

Flows

Database keys for the ENR flow structures and daily stage gages are listed in **Table 4**. Since February 1999, the operation of the ENR has been modified due to the transition to STA-1W. The old ENR seepage canal was plugged at the end of February 1999 and structure G-250S_P no longer pumped ENR seepage. The sheet pile that separated the ENR supply canal from the ENR seepage canal was removed in the middle of March 1999. Between March 1999 and the beginning of July 1999, G-250S_P was used as inflow pump for the ENR.

The total inflow pumping for the 315 days (August 20, 1998 to June 30, 1999) was 7,620 ha-m (61,774 ac-ft) and the total outflow through the outflow pump station was 7,768 ha-m (62,974 ac-ft). G-250S_P started its current operation of pumping seepage and discharge from Cell 5 of STA-1W into the remaining cells (Cells 1, 2, 3 and 4) in July 1999. The daily pumping volumes of the inflow and outflow pumps are shown in **Figure 4**. **Figure 5** shows daily pumping rates of the seepage pump and seepage flow through L-7 levee roadside seepage collection culverts. The L-7 seepage through the roadside culverts was estimated using a regression equation developed from 42 data points. A relationship was developed between the seepage from L-7 through the roadside culverts and the stage rise in WCA 1 above 4.57 m (15 ft) NGVD, and the difference in stages between WCA 1 and the eastern cells of the ENR (Guardo, 1996). The regression had a coefficient of determination (\mathbb{R}^2) of 0.93 and a standard error of 0.30 m³ s⁻¹. The equation is given as follows:

$$L7seepage = 0.217 \Delta WCA^{1.311} * \Delta h^{2.025}$$
(1)

where L-7 seepage is in $m^3 s^{-1}$; Δ_{WCA} is the rise in stage in WCA 1 above 4.57 m (15 ft) NGVD and Δh is the difference in stage between WCA 1 and the eastern cells of the ENR. The total estimated seepage from L-7 through the roadside culverts was 426 ha-m (3,453 ac-ft). Monthly flow data for the study period are presented in **Table 3**.

			,	•
Station	Description	Location	DBKEY	Remark
G-250_P	Pump	Feeder Canal/Buffer Cell	15847,16222	inflow
G-250S_P	Pump	Seepage Canal/Buffer Cell	15846, JK278	seepage return, Inflow
G-251_P	Pump	Cell 4/WCA 1	15848	outflow
G-258_C	Culvert	Cell 3/Seepage Canal	15940	recycle
G-259_C	Culvert	Cell 4/Seepage Canal	15939	recycle
G-251_T	Stage	G-251_P tailwater	16219	WČAI
G-255_H	Stage	Buffer Cell/Cell 2	15908	headwater
ENR101	Stage	Cell 1	15850	center of cell
G-253EF_H	Stage	Cell 1/Cell 3	15897	headwater
G-255_T	Stage	Buffer Cell/Cell 2	15909	headwater
ENR203	Stage	Cell 2	15873	center
G-254C_H	Stage	Cell 2/Cell 4	15903	headwater
G-253EF_T	Stage	Cell 1/Cell 3	15898	tailwater
ENR301	Stage	Cell 3	15876	center
ENR012	Stage	Cell 3	15849	upstream of G-251_P
G-254C_T	Stage	Cell 2/Cell 4	15904	tailwater
ENR401	Stage	Cell 4	15727	center of cell
G-256_H	Stage	Cell 4B/Discharge Canal	15910	headwater
ENR003	Stage	East end of Buffer Cell	15812	WCA1 (discontinued 5/7/99)
ENR004	Stage	L7 canal at junction of ENR	15842	WCA1 (discontinued 5/7/99)
ENR005	Stage	L7 canal near G-251	15843	WCA1 (discontinued 5/7/99)

Table 4. Flow control structures, stage recorders and database retrieval keys used in the water budget analysis of the ENR.

,

Π

ī

.



Figure 4. Daily pumping rates of inflow and outflow pumps in ENR



Figure 5. Daily pumping rates of the seepage pump and seepage flow through L-7 levee roadside seepage collection culverts in ENR

Water Levels

Daily water levels in each cell of the ENR are dependent on rainfall, evapotranspiration, seepage and daily operational decisions. Water levels have been regulated based on water depth, operation status of the S-5A pump station, pump maintenance, and other activities in ENR such as dye studies and construction operations. The minimum, maximum, and mean of the daily average stage observations for the study period are shown in **Table 5**. The mean observed stage in the Buffer Cell was 3.62 m (11.88 ft) NGVD. The mean stage in Cell 1 was 3.58 m (11.75 ft) and the mean stage in Cell 2 was 3.59 m (11.78 ft) NGVD. The mean stage in Cell 3 was 3.44 m (11.29 ft) NGVD and the mean stage in Cell 4 was 3.55 m (11.65 ft) NGVD. Average daily water level observations in the eastern treatment train of the ENR are shown in **Figure 6**, while those in the western treatment train are shown in **Figure 7**. The mean water depths for ENR cells, Buffer Cell 1, Cell 2, Cell 3 and Cell 4 were 52 cm (20.5 in), 45 cm (17.7 in), 65 cm (25.6 in), 34 cm (13.4 in) and 55 cm (21.7 in), respectively.

	Wa	ater Surface Elevation		Depth	
Cell	Min. m (ft) NGVD	Max. m (ft) NGVD	Mean m (ft) NGVD	Mean cm (in)	
Buffer	3.33 (10.93)	3.94 (12.93)	3.62 (11.88)	52 (20.5)	
Cell 1	3.34 (10.96)	3.92 (12.86)	3.58 (11.75)	45 (17.7)	
Cell 2	3.31 (10.86)	3.92 (12.86)	3.59 (11.78)	65 (25.6)	
Cell 3	3.28 (10.76)	3.80 (12.47)	3.44 (11.29)	34 (13.4)	
Cell 4	3.29 (10.79)	3.89 (12.76)	3.55 (11.65)	55 (21.7)	

Table 5. Observed water surface elevations and depths in the ENR (August 20, 1998 to June 30, 1999).



Figure 6. Daily mean water levels in the eastern cells of the ENR and the Buffer Cell



Figure 7. Daily mean water levels in the western cells of the ENR and the Buffer Cell

ENR WATER BUDGET COMPUTATIONS

ENR Water Balance Model

A schematic hydrologic model for the ENR is depicted in Figure 8. The influent pumped through the inflow pumps accounts for about 78% of the known inflow to the system. The known inflows to the system are the G-250 and G-250S pump stations inflows, rainfall, and seepage through the roadside L-7 levee culverts (L-7a). From March 1999 to July 1999, G-250S was operated as inflow to ENR. Rainfall accounts for 18% and seepage through the roadside culverts (L-7) accounts for 4%. Outflow pumping (G-251) accounts for 81% of the outflows, with evapotranspiration constituting 18% of the total outflows. The unknowns in the system are subsurface inflows, outflows and errors that account for 1%. The schematic model (Figure 8) and the following set of water balance equations represent the hydrologic system of the ENR for water budget analysis purposes:

$$INFLOW - OUTFLOW = \Delta S + \varepsilon_T$$
⁽²⁾

where INFLOW is the amount of water that enters the system from external sources, and OUTFLOW is water that leaves the system boundary and is not recirculated. ΔS is the change in storage in the system during the time interval of interest. Sum of all errors is represented by ε_T . Because all inflow and outflow cannot be entirely quantified, the following equation is introduced to represent the remainders, errors and unknowns:

$$REMAINDERS = \varepsilon_{T} + UNKNOWNS$$
(3)

Figure 8 shows the possible inflows and outflows to and from the ENR system. The seepage canal, which encompasses the northern and western sides of the ENR, was designed and operated to capture seepage from the ENR to the neighboring farms.

When opened, and/or through leakage, G-258 and G-259 culverts release water into the seepage canal. Seepage through the western and northern ENR levees is represented in the model by SEEPAGE 2, regardless of the magnitude. SEEPAGE 3 represents the two seepage possibilities into or out of the seepage canal from or to the surrounding farms, regardless of the magnitude. SEEPAGE 1 represents the possible seepage loss through the southern ENR levee into Knight's Farm. The unmeasured seepage flow from WCA 1 into the ENR is represented by L-7b. Researchs on ENR groundwater flow are reported in Guardo and Prymas (1998), and Choi and Harvey (2000). Groundwater mass balance is beyond the scope of this study.

In computing the water balance for the ENR, it is essential to identify quantifiable variables from unquantifiable variables, making reasonable assumptions to reduce the quantity of unknowns as much as possible. Since the purpose of the seepage canal is to recirculate seepage and recycled water, it is assumed that the seepage return pump flows (G-250S) are recirculated in the system as designed. The G-250S ENR seepage recirculation ended in March 1999 as part of STA-1W construction. Seepage recirculation is described or represented in the following equation:

$$S_p = SEEPAGE 2 + \varepsilon_R \tag{4}$$



Figure 8. Schematic hydrologic model for the ENR

where S_P is seepage return pump flows (G-250S); SEEPAGE 2 is seepage from ENR to the seepage canal; and ε_R is error in assumption and all other errors including measurement errors and calibration errors. The error term also includes the net effect of unknown variable SEEPAGE 3 which is the net subsurface flow of water from the seepage canal to the adjacent farms (west and north) or from the farms to the seepage canal. Also, SEEPAGE 1 (seepage through the southern levee of the ENR) and L-7b (subsurface seepage from WCA 1 that is not captured by the roadside culverts) are also unknowns. Equation 2 is expanded as follows:

$$\Delta S = G250 + R + L7a + L7b - G251 - ET - SEEPAGE I + \varepsilon_R + \varepsilon_I + \varepsilon_0$$
(5)

where ΔS is change in storage in the system; G-250 is inflow pump flows; R is rainfall; L-7a is seepage flows from WCA 1 through the roadside culverts; L-7b is unknown seepage subsurface flow from WCA 1 into the ENR; ET is evapotranspiration losses; SEEPAGE 1 is seepage loss through the southern levee of the ENR; ε_R represents errors in accounting for the recirculation water in the system; ε_I represents errors in inflow terms; and ε_0 represents errors in outflow terms. The total error in the system is expressed as follows:

$$\varepsilon_T = \varepsilon_R + \varepsilon_I + \varepsilon_0 \tag{6}$$

Daily change in storage for the ENR was computed as a sum of storage changes in each of the five cells (Buffer Cell, Cell 1, Cell 2, Cell 3 and Cell 4). Change in storage volume in each cell was computed from the area of the cell and change in stage. Change in stage was computed as the difference between consecutive daily mean stage readings averaged from two or three locations in each cell (**Table 5**).

The remainders in the computation of daily water balances are the sum of all errors and unknowns in the system. Daily remainders were computed for the study period based on the following equation:

$$REMAINDERS = \mathcal{E}_{T} + SEEPAGE \ l + L7b \tag{7}$$

where ε_T is the sum of all errors, SEEPAGE 1 is seepage from the ENR through the southern levee, and L-7b is seepage from WCA 1 into the ENR that is unaccounted for in the water budget.

Discussion

The total inflow through the inflow pump was 7,620 ha-m (61,774 ac-ft) and almost equaled the total outflow through the outflow pump, which was 7,768 ha-m (62,974 ac-ft). Seepage inflow from the L-7 levee through the roadside culverts was 426 ha-m (3,453 ac-ft). There was no flow data indicating flows through culverts G-258 and G-259. The seepage recirculation pump had a total flow of 2,519 ha-m (20,421 ac-ft). Total average areal rainfall for the study period was 115.2 cm (45.4 in) and the total average areal evapotranspiration was 108.6 cm (42.8 in).

For the study period, the mean daily remainders (errors and unknowns) was -0.30 hectare-meters per day (ha-m d⁻¹) or -2.43 acre-feet per day (ac-ft d⁻¹) with the total remainders being -97 ha-m (-786 ac-ft). The standard deviation of the remainders is 20.57 ha-m d⁻¹ (167 ac-ft d⁻¹) which signifies high variation. **Figure 9** depicts the daily remainders distribution. The negative remainder indicates that there is an overall outflow from the system through unidentified directions. The remainder is 1% of the inflows or the outflows. Summary of the water budget is shown in **Table 6**. Details of the water balance terms and calculations are shown in **Appendix 1**.

The mean hydraulic loading rate for the study period, based on the pump inflow, was 1.57 centimeters per day (cm d⁻¹) or 0.62 inches per day (in d⁻¹). The mean hydraulic retention time was computed as the ratio of the mean-estimated volume of water of the ENR and the average daily outflow pumping rate. The mean estimated volume was computed from the area-weighted (by cell) mean depth of 48.7 cm (19.2 in) and total area of 1544 ha (3,815 ac). The estimated mean hydraulic retention time was 30.5 days. Comparison of the current year ENR water budget components and the previous two years is shown in **Table 7**.



Figure 9. Distribution of daily remainders (errors and unknowns) from the ENR water balance

1999).
ne 30,
to Ju
1998
1,20,
(Augus
e ENR -
af th
budget o
: water
of the
Summary
Table 6.

		· · · · · · · · · · · · · · · · · · ·			
SMOTHNI	ha-m	Percent of Total	OUTFLOWS	ha-m	Percent of Total
Inflow Pump	7,620	77.6%	Outflow Pump	7,768	81.4%
Rain	1,778	18.1%	ET	1,677	17.6%
L-7 Culverts (L7a)	426	4.3%	Remainders	16	1%
Total	9,824	100%	Total	9,542	%001
Change in Storage	282				

	, ,		•	
	8/19/94 to 8/19/96 (2 years)	8/20/96 to 8/19/97 (1 year)	8/20/97 to 8/19/98 (1 year)	8/20/98 to 6/30/99 (315 days)
INFLOWS (ha-m)				
Inflow pump	39,000	11,972	12,025	7,620
Rain	5,068	2,108	1,938	1,778
L-7 Culverts (L7a)	1,198	431	757	426
Total	45,266	14,511	14,720	9,824
OUTFLOWS (ha-m)				
Outflow pump	38,802	11,872	11,450	7,768
ET	4,050	2,008	2,074	1,677
Remainders	2,781	547	1,349	<u>97</u>
Total	45,633	14,427	14,873	9,542
Change in Storage (ha-m)	-367	83	-153	282
Seepage recirculation				
Seepage pump (ha-m)	7,143	3,385	3,248	2,519
Loading Rate (cm d ⁻¹)	3.45	2.12	2.13	1.57
Average depth (cm)	57.5	52	54.1	48.7
Retention time (days)	17	24.5	25.4	30.5

.

20

.

Table 7. Comparison of ENR water budget (1998-1999) components with the previous four years.

ENR WATER BUDGET SUMMARY

The ENR was in full operation for five years. This water budget study covers the last year of its operation before being part of STA-1W (August 20, 1998 to June 30, 1999). For the period of analysis, the total inflow through the inflow pump was 7,620 hectare-meters (ha-m) or 61,774 acrefeet (ac-ft) and the total outflow through the outflow pump was 7,768 ha-m (62,974 ac-ft). Seepage inflow from the L-7 levee through the roadside culverts was a total of 426 ha-m (3,453 ac-ft). The seepage recirculation pump had a total flow of 2,519 ha-m (20,421 ac-ft) and there was no flow data indicating flows through culverts G-258 and G-259. Total areal average rainfall for the study period was 115.2 centimeters (cm) or 45.4 inches (in) and the total areal average evapotranspiration was 108.6 cm (42.8 in). The remainders in the water balance, the sum of the errors and unknowns, was 1% of the inflows into the system.

The mean hydraulic loading rate for the one-year period, based on the G-250 pump inflow, was 1.57 centimeters per day (cm d⁻¹) or 0.62 inches per day (in d⁻¹). The loading rate for this study period was lower than previous years. The mean hydraulic retention time was computed as the ratio of the mean estimated volume of water of the ENR and the average daily outflow pumping rate. The mean-estimated volume was computed from the area-weighted (by cell) mean depth of 48.7 cm (19.2. in) and total area of 1544 ha (3,815 ac). The estimated mean hydraulic retention time was 30.5 days. In the ENR, all hydrologic parameters, with the exception of seepage through the system, are well monitored. Since seepage is not only in one direction, the remainders (errors and unknowns) could not be allocated to one variable.

SECTION II

STORMWATER TREATMENT AREA 1 WEST (STA-1W)

Site Description

The STA-1W project is one of the components of the Everglades Construction Project. It incorporates the ENR and expands northerly with the addition of Cell 5. The total area is 2,772 ha (6,849 acres) with Cell 5 covering 1,228 ha (3,034 acres).

Vegetation Cover and Monitoring

As part of the ENR monitoring plan, temporal and spatial changes of vegetation have been documented using quarterly aerial photography prior to 1995 and semi-annually since 1995. Vegetation cover for Cells 1, 2, 3, and 4 of the ENR estimated from an aerial photograph of April 13, 1999 is shown as vegetation cover estimate for STA-1W (**Table 8**). Based on estimates from aerial photograph, Cell 5 has 55% of emergent and submerged aquatic vegetation and 45% of open water (**Table 8**).

STA-1W SYSTEM HYDRAULICS AND OPERATION

System Hydraulics

STA-1W Inflow and Distribution

West Palm Beach (C-51) canal water that would have been otherwise pumped into the Loxahatchee Wildlife Refuge (WCA1) via the S5-A Pump Station and flow through the refuge is diverted to STA-1W. A small portion of the area of WCA1 near S5A pump station is leveed and forms the STA-1 Inflow and Distribution area (STA-1 I & D) that serves as a storage area to divert water into STA-1W (and into STA-1E when it is built). There are two old and four new water control structures in the STA1 I & D. The S5A pump station delivers water from C-51 (West Palm Beach canal); the S5AS spillway controls inflow and outflow at the junction of L-8 and C-51. The junction has culvert structures S5AW and S5AE. S5AS normally releases water from WCA1 to L-8 canal or vice versa. The four new spillway structures are G-300, G-301, G-302 and G-311.

Table 8. Site characteristics of Stormwater Treatment Area 1 West.

Cell	Area	Average Ground Elev	÷		Land Cover*		
	ha (ac)	m (ft) NGVD	Cattails (%)	Algac/Macrophyte complex (%)	Floating aquatics (%)	Mixed veg. (%)	Open water/ Submerged aquatics (%)
Cell 1**	580 (1433)	3.13 (10.25)	30	0	6	22	39
Cell 2	414 (1023)	2.94 (9.65)	46	0	11	7	41
Cell 3	404 (998)	3.10 (10.18)	47	0	1	42	10
Cell 4	146 (361)	3.00 (9.83)	5	78	m	I	15
Cell 5	1228 (3034)	2.90 (9.50)	##	##	#	##	##
Total	2772 (6849)	2.99 (9.79)#	1		[-	

* land cover for ENR (based on April 13, 1999 observation); Cell 5 land coverage was based on estimate from aerial photo taken in August 2000

** most of the western levee between old ENR Buffer Cell and Cell 1 is degraded forming a larger Cell 1 (580 ha)

area-weighted average ground elevation 35%; open water, 45%

G-300 is a 2-bay reinforced concrete U-shaped spillway with vertical lift gates installed on the crest of an ogee shaped weir. The purpose of this structure is to bypass flows from the STA-1 I & D area into the L-40 borrow canal which runs along the eastern edges of WCA1. G-301 is a 3-bay reinforced concrete U-shaped spillway with vertical lift gates on crest of weir. The purpose of this structure is to bypass flow from the STA-1 I & D area into WCA1 along the L-7 borrow canal on the western edge of WCA1. G-302 is a fixed-crest concrete ogee spillway equipped with two vertical lift gates 6 meters (20 ft) wide each. The purpose of this structure is to supply inflow to the five cells of STA-1W from the STA-1 I & D area and has a capacity of 92 m³ s⁻¹ (3,250 cfs). G-311 is a 3-bay reinforced concrete spillway with lift gates on crest of weir. The purpose of this structure is to supply water for the future STA-1E from the STA-1 I & D area. Information for STA-1W structures is provided in **Table 9**. The monitoring network of STA-1W is shown in **Figure 10**.

STA-1W Internal and Discharge Structures

The Supply Canal to STA-1W is about 2.72 km (1.7 miles) long extending between the inflow structure G-302 and the structure controlling flow into Cells 1,2 3, and 4 (G-303). The canal has side slopes of 2.5:1 with bottom width of 18.3 m (60 ft) at elevation -1.52 m (-5 ft), NGVD. Expected velocities in the inflow canal vary between 0.232 m s⁻¹ (0.76 ft s⁻¹) and 0.418 m s⁻¹ (1.37 ft s⁻¹) (Hutcheon Engineers, 1996). G-303 is a 2-bay ogee spillway equipped with two lift gates of 4.9 m (16 ft) width and with discharge capacity of 50.4 m³ s⁻¹ (1780 cfs). Inflow to Cell 5 is through ten 29.3 m (96 ft) long corrugated metal pipe culverts (G-304A-J). The combined capacity of the inflow culverts (G-304A-J) is 41.6 m³ s⁻¹ (1470 cfs). The Florida Power Line (FPL) levee runs across Cell 5. Twenty-two culverts (G-305A-V) were constructed to deliver water from the eastern part to the western part of the cell. Each of the G-305 culverts is 213 cm (84 inches) in diameter and 27.4 m (90 ft) long with an invert elevation of 1.07 m (3.5 ft) NGVD. Seepage and recirculated water from Cell 5 is pumped through G-250S to Cell 1 through the old ENR Buffer Cell which is now part of Cell 1. G-250S has three main pumps with combined capacity of 5.66 m³ s⁻¹ (200 cfs) and three supplemental pumps from the old ENR inflow pump station G-250 with a combined capacity of 8.49 m³ s⁻¹ (300 cfs).

Outflow from Cell 5 to the discharge canal is through ten corrugated metal pipes of 183 cm (72 inches) diameter and 39.6 m (130 ft) long with a combined discharge capacity of 41.6 m³ s⁻¹ (1470 cfs). During the study period, Cell 5 flow that was released to the discharge canal was recirculated to the other cells (1, 2, 3 and 4) via culverts G-327A, G-327C and the G-250S pump station. G-327A is a gated culvert with 213 cm (84 inches) diameter, 39.6 m (130 ft) length and 2.83 m³ s⁻¹ (100 cfs) discharge capacity. G-327C is a culvert with 39.3 m (129 ft) length and 2.83 m³ s⁻¹ (100 cfs) discharge capacity. STA-1W outflow structures are G-251 and G-310 pump stations. G-251 has six identical pumps with a combined capacity of 12.74 m³ s⁻¹ (450 cfs). During the study period the only outflow from STA-1W was through G-251 as the construction of G-310 was not complete. G-310 is equipped with six pumps of three different capacities with a total capacity of 86 m³ s⁻¹ (3,040 cfs). G-310 has two electric pumps with combined discharge capacity of 5.66 m³ s⁻¹ (200 cfs); two diesel pumps with combined discharge capacity of 26.6 m³ s⁻¹ (940 cfs) and two diesel pumps with combined discharge capacity of 53.8 m³ s⁻¹ (1,900 cfs).

G-251	chutch	6	12.7 m ³ s ^{-t} (450 cfs)	Ð	12.7 m ² s ⁻¹ (450 cfs)					0.91 m (3 ft) dia.		200
G-310	domd	6	86 m² s² ¹ (3040 cfs)	0	86 m ³ s ⁻¹ (3040 cfs)	2.74 m (9 ft)						720
G-327A	colvert	-	5.7 m ³ s ⁻¹ (200 cfs)	0	$2.83 \text{ m}^3 \text{ s}^3$ (100 cfs)	2.74 m (9 ft)	2.65 m (8.7 ft)	5.33 m (18.8 ft)	0.15 m (0.5 ft)	2.13 m (7 ft) dia.		
G-309	spillway		28.3 m ³ s ⁻¹ (1000 cfs)	0	15.8 m ³ s ⁻¹ (560 cfs)	3.84 m (12.6 ft)	2.38 m (7.8 ft)	5.03 m (16.5 ft)	2.32 m (7.6 ft)	4.27 m (14 ft)	2.04 m (6.7 ft)	
G-308	spiłway	Ħ	28.3 m ³ s ⁻¹ (1000 cfs)	0	15.8 m ³ s ⁻¹ (560 cfs)	3.58 m (11.75 ft)	2.29 m (1.5 ft)	5.03 m (16.5 ft)	2.26 m (7.4 li)	4.27 m (14 ft)	2.04 m (6.7 ft)	
G-306	culvert	01	41.6 m ³ s ⁻¹ (1470 cfs)	0	41.6 m ³ s ⁻¹ (1470 cfs)	3.51 m (11.5 ft)	2.74 m (9 ft)	5.73 m (18.8 ft)	2.38 m (7.8 ft) iav	1.83 m (6 ft) dia.		
G-304	culvert	9	41.6 m ³ s ⁻¹ (1470 cfs)	0	41.6 m ³ s ⁻¹ (1470 cfs)	4.79 m (15.7 ft)		5.73 m (18.8 ft)	3.43 m 1.52 m (11.25 ft) (5 ft inv)	1.83 m (6 ft) dia.		
G-303	spillway	17	50.4 m ³ s ⁻¹ (1780 cfs)	0	50.4 m ³ s ⁻¹ . (1780 cfs)	4.79 m (15.7 ft)	4.41 m (14.46 ft)			4.88 m (16 ft)		
G-302	spillway	7	92 m [°] s ⁻¹ (3250 cfs)	0	92 m ³ s ^{-t} (3250 cfs)	5.49 m (18 ft)	4.79 m (15.7 ft)		2.87 m (9.4 ft)	6.1 m (20 ft)		
G-301	spillway	۳.		-28.3 m ³ s ⁻¹ (-1000 cfs)		5.79 m (19 ft)		6.71 m (22 ft)	2.35 m (7.7 ft)	6.71 m (22 ft)	3.57 m (11.7 ft)	
G-300	spiliway	2		-28.3 m ³ s ⁻¹ - (-1000 cfs)		5.79 II (19 ft)		6.71 m (22 ft)	3.35 m (11 ft)	6-1 m (20 R)	2.56 m (8.4 ft)	
Station	Type	Units	Max Q	Min Q	Design Q	Design HW	Design TW	Bypass stage	Flow Min. Elevation	Flow Width	Flow Height	RPM

Table 9. Structure information for STA-1W stations.



Figure 10. STA-1W structures and monitoring network
Discharge from Cell 1 into Cell 3 flows through ten 183 cm (72 inches) diameter and 17.7 m (58-ft) long culverts (G-253A-J). Discharge from Cell 2 into Cell 4 flows through nine 183 cm (72 inches) diameter and 16.5 m (54 ft) long culverts (G-252A, A1, B, B1, C, C1, D, D1 and E). Discharge from Cell 3 is to the discharge canal through G-308 and G-259 and to WCA1 through G-251 pump station. G-308 is a gated weir with discharge capacity of 15.85 m³ s⁻¹ (560 cfs) and G-259 is a gated culvert of 183 cm (72 inches) diameter and 23.9 m (78.5 ft) long. Discharge from Cell 4 is into the discharge canal and into Cell 3 through G-309, G-258 and G-256A-E. G-309 is a gated weir with discharge capacity of 15.85 m³ s⁻¹ (560 cfs) and G-258 is a gated culvert of 183 cm (72 inches) diameter and 23.9 m (78.5 ft) long. Discharge from Cell 4 is into the discharge capacity of 15.85 m³ s⁻¹ (560 cfs) and G-256A-E. G-309 is a gated weir with discharge capacity of 15.85 m³ s⁻¹ (560 cfs) and G-258 is a gated culvert of 183 cm (72 inches) diameter and 23.5 m (77 ft) long. G-256A-E consists of five culverts of 183 cm (72 inches) diameter and 16.6 m (54.5 ft) length.

The outflow canal extends between G-327A at the northwest corner and G-310 pump station at the southwestern corner. The discharge canal is about 9.12 km (5.7 miles) long with bottom width varying from 15.2 m (50 ft) at G-327A to 24.4 m (80 ft) at G-308 and to 30.5 m (100 ft) at G-259 in order to account for changes in flow magnitude and ground elevation.

Operation

S5A diverts water from the West Palm Beach canal into the STA-1 Inflow and Distribution (STA-1 I&D) area. From the STA-1 I & D area, water flows to STA-1W through spillway G-302 or can be bypassed to WCA1 through G-300 and G-301 when the need arises. Water flows into Cell 5 via the Inflow Canal and through culverts G-304 A-J, and into treatment Cells 1, 2, 3 and 4 through gated weir structure G-303. The old ENR seepage pumps (G-250S) control stages in the seepage canal north of Treatment Cell 5 and redirect flow to the old ENR (Cells 1, 2, 3 and 4). Outflow from STA-1W was through pump station G-251, as pump station G-310 was not completed. One objective of operation was maintaining stage in Cell 5 at 3.41 m (11.2 ft) NGVD with a fluctuation of 0.06 m (0.2 ft).

Transitional Operation of Cell 5

During the transition period from ENR to STA-1W, Cell 5 was maintained full with flows through G-302, while the remaining four cells were operated according to the operation plan described in Section I. During that period, water delivery to the ENR came from the West Palm Beach Canal, through the supply canal and pump G-250 until July 1999. Culverts were installed for flow delivery across G-302 connecting two segments of the supply canal. After the seepage canal was completed and connected to G-250S, the seepage from Cell 5 was returned into the existing ENR treatment Cells 1, 2, 3 and 4 via the culvert under G-302 and through the scepage pumps G-250S.

STA-1W HYDROLOGY AND HYDROLOGIC MONITORING

Rainfall

STA-1W has a six-gauge rainfall network. **Table 10** lists all the rainfall gaging stations, the corresponding database keys and respective Thiessen weights. Figure 10 shows the gage locations. Areal average rainfall on the project site was computed as a Thiessen-weighted average of the six-gage network. The few instances of data gaps at some of the stations were filled by estimating the rainfall from the closest gage. The daily distribution of areal average rainfall for the study period (July 1, 1999 to June 30, 2000) is depicted in Figure 11. Monthly summary of areal average rainfall for the STA-1W is shown in Table 11. The total areal average rainfall for STA-1W (July 1, 1999 to June 30, 2000) was 100.8 cm (39.7 in). The annual rainfall was below the average rainfall for the area. The average areal rainfall for the constructed wetland from August 19, 1994 to August 20, 1999 was 144.3 cm (56.8 inches).

Stations	DBKEY	Thiessen Weights
ENR101	15851	0.087
ENR106	DU515	0.441
ENR203	15874	0.222
ENR301	15877	0.126
ENR308	15888	0.049
ENR401	15862	0.075

Table 10. Rainfall stations in STA-1W, database retrieval keys and Thiessen weights.

Evapotranspiration

Daily evapotranspiration is computed from high resolution weather data using a radiation-based evapotranspiration estimation model that was based on lysimeter studies in the ENR (Abtew, 1996a, 1996b). A complete weather station is located in Cell 3 (ENR308). The daily distribution of evapotranspiration for STA-1W for the study (July 1, 1999 to June 30, 2000) is depicted in Figure 11. Monthly summary of evapotranspiration for STA-1W is shown in Table 11. The total evapotranspiration for STA-1W (July 1, 1999 to June 30, 2000) was 137.6 cm (54.2 inches). The high ET is a reflection of the drier than normal rainfall conditions. The five-year (August 19, 1994 to August 20, 1999) average ET for the ENR was 131.3 cm (51.7 inches).



Table 11. STA-1W monthly flows, areal weighted rainfall and ET (July 1, 1999 to June 30, 2000).

Seepage L-7 culverts ha-m	8 7 8 6 7 6 7 8 7 8 7 8 8 7 8 9 7 9 7 9 7 9 7 9 7 9
Seepage and recirculation pump G-250_S + G-250_P ha-m	118 628 730 753 753 755 756 757 722
ET cm (in)	13.61 (5.36) 12 (4.73) 10.54 (4.15) 9.70 (3.82) 8.39 (3.30) 6.95 (2.74) 9.11 (3.59) 10.02 (3.94) 12.49 (4.92) 14.26 (5.61) 14.26 (5.61) 16.58 (6.53) 13.98 (5.50)
Rainfall cm (in)	$\begin{array}{c} 6.43 \ (2.53) \\ 14.50 \ (5.7) \\ 15.62 \ (6.15) \\ 30.80 \ (12.13) \\ 0.87 \ (0.34) \\ 2.19 \ (0.86) \\ 1.92 \ (0.76) \\ 2.04 \ (0.80) \\ 9.47 \ (3.73) \\ 11.05 \ (4.35) \\ 2.28 \ (0.90) \\ 3.61 \ (1.42) \end{array}$
Outflow G-251 ha-m	541 490 2015 2323 1320 1574 1196 1196 1196 1196
Inflow G-302_S ha-m	11 0 2413 2018 1194 1194 1294 1294 1295 1386 1386 1386 1386 1386 1386
Month	July Aug Sept Oct Oct Jan May May
Year	$\begin{array}{c} 1939\\ 1939\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\ 2000\\$

30

Flows

Database keys for STA-1W flow structures and stage gages are listed in **Table 12**. The total inflow spillway discharge for the study period (July 1, 1999 to June 30, 2000), was 14,636 ha-m (118,651 ac-ft) and the total outflow through the outflow pump station was 14,977 ha-m (121,416 ac-ft). G-250S_P started its current operation of pumping seepage and discharge from Cell 5 of STA-1W into the remaining cells (Cells 1, 2, 3 and 4). The daily pumping rates of the inflow and outflow pumps are shown in **Figure 12**. **Figure 13** shows estimated seepage from the L-7 levee flowing through the roadside culverts and the daily seepage recycling pumping. The total seepage and recirculation pumping was 6,688 ha-m (54,218 ac-ft). The L-7 seepage through the roadside culverts was estimated using a regression equation developed from 42 data points. A relationship was developed between the seepage from L-7 through the roadside culverts and the difference in stages between WCA 1 and the eastern cells of the ENR (Guardo, 1996). The regression had a coefficient of determination (R²) of 0.93 and a standard error of 0.30 m³ s⁻¹ (Equation 1). The total estimated seepage from L-7 through the roadside culverts was 438 ha-m (3,551 ac-ft). Monthly flow data for the study period are presented in **Table 11**.

Water Levels

Daily water levels in each cell of STA-1W depend on rainfall, evapotranspiration, scepage and daily operational decisions. Water levels have been regulated based on water depth, operation status of the S5A pump station, pump maintenance and construction. The minimum, maximum, and mean of the daily average stage observations for the study period are shown in **Table 13**. The mean observed stage in Cell 1 was 3.70 m (12.14 ft) NGVD. The mean stage in Cell 2 was 3.71 m (12.17 ft) and the mean stage in Cell 3 was 3.48 m (11.42 ft) NGVD. The mean stage in Cell 4 was 3.65 m (11.98 ft) NGVD and the mean stage in Cell 5 was 3.34 m (10.96 ft) NGVD. Average daily stages for Cell 5 were computed from manual stage readings for G-304 tailwater, G-305 headwater, and G-306 headwater from operation archive data and hardcopies from construction site. Daily data are shown in **Appendix II**. Average daily water level observations in the eastern treatment train of STA-1W are shown in **Figure 14**, while those in the western treatment train are shown in **Figure 15**. **Figure 16** shows daily water levels for Cell 5 during the transitional and operation stages of STA-1W. The mean water depths for Cells 1, 2, 3, 4 and 5 were 57 cm (22.4 in), 77 cm (30.3 in), 38 cm (15 in), 65 cm (25.6 in) and 44 cm (17.3 in), respectively.

Station	Description	Location	DBKEY	Remark
G-302	Spillway	I&D/Supply Canal	JW221	inflow
G-250S_P	Pump	Seepage Canal/Cell 1	JK278	seepage return, recirculation
G-251_P	Pump	Cell 4/WCA 1	JW222	outflow
G-252IJ_T	Stage	Old Buffer Cell/Cell I	15894	tailwater
ENR101	Stage	Cell 1	15850	center of cell
G-253EF_H	Stage	Cell 1/Cell 3	15897	hcadwatcr
G-255_T	Stage	Buffer Cell/Cell 2	15909	headwater
ENR203	Stage	Cell 2	15873	center
G-254C_H	Stage	Cell 2/Cell 4	15903	headwater
G-253EF_T	Stage	Cell 1/Cell 3	15898	tailwater
ENR301	Stage	Cell 3	15876	center
ENR012	Stage	Cell 3	15849	upstream of G-251_P
G-254C_T	Stage	Cell 2/Cell 4	15904	tailwater
ENR401	Stage	Cell 4	15727	center of cell
G-256_H	Stage	Cell 4B/Discharge Canal	15910	headwater
G-304E_T	Stage	Supply Canal/Cell 5	L9842	tailwater
G-304J_T	Stage	Supply Canal/Cell 5	L9843	tailwater
G-306A_H	Stage	Cell 5/discharge Canal	12951	beadwater
G-306J_H	Stage	Cell 5/discharge Canal	L9954	headwater
G-251_T	Stage	G-251_P tailwater	16219	WCAI

Table 12. Flow control structures, stage recorders and database retrieval keys used in the water budget analysis for STA-1W.

32



Figure 12. Daily STA-1W inflows and outflows



Figure 13. Daily pumping rates of the seepage/recirculation pump and seepage flow through L-7 levee roadside seepage collection culverts in STA-1W

	Water	Surface Elevation		Depth	
Cell	Min. m (ft) NGVD	Max. m (ft) NGVD	Mean m (ft) NGVD	Mean cm (in)	
Cell 1	3.40 (11.14)	4.11 (13.48)	3.70 (12.14)	57 (22.4)	
Cell 2	3.43 (11.26)	4.10 (13.45)	3.71 (12.17)	77 (30.3)	
Cell 3	3.26 (10.70)	3.99 (13.09)	3.48 (11.42)	38 (15.0)	
Cell 4	3.33 (10.93)	4.06 (13.32)	3.65 (11.98)	65 (25.6)	
Cell 5*	3.07 (10.07)	3.81 (12.50)	3.34 (10.96)	44 (17.3)	

 Table 13. Observed water surface elevations and depths in STA-1W (July 1, 1999 to June 30, 2000).

* estimated from operation and construction site records



Figure 14. Daily mean water levels in Cells 1 and 3 of STA-1W



Figure 15. Daily mean water levels in Cells 2 and 4 of STA-1W



Figure 16. Daily mean water levels in Cell 5 of STA-1W

STA-1W WATER BUDGET COMPUTATIONS

STA-1W Water Balance Model

A schematic hydrologic model for STA-1W is depicted in Figure 17. The influent supplied through the G-302 spillway accounts for about 81.0% of the known inflow to the system. The known inflows to the system are G-302 spillway inflows, rainfall, and seepage through the roadside L-7 levee culverts (L-7a). Rainfall accounts for 15.5% and seepage through the roadside culverts (L-7a) accounts for 2.4%. Outflow pumping (G-251) accounts for 79.7% of the outflows, with evapotranspiration constituting 20.3% of the total outflows. The unknowns in the system are ungaged surface flows during construction, subsurface inflows, outflows and errors that account for 1.1%. The schematic model (Figure 17) and the following set of water balance equations represent the hydrologic system of STA-1W for water budget analysis purposes.

$$INFLOW - OUTFLOW = \Delta S + \varepsilon_T \tag{8}$$

where INFLOW is the amount of water that enters the system from external sources, and OUTFLOW is water that leaves the system boundary and is not recirculated. ΔS is the change in storage in the system during the time interval of interest. Sum of all errors is represented by ε_T . Because all inflow and outflow can not be entirely quantified, the following equation is introduced to represent the remainders, errors and unknowns:

$$REMAINDERS = E_T + UNKNOWNS \tag{9}$$

Figure 17 shows the possible inflows and outflows to and from STA-1W system. The seepage canal, which encompasses the northern side of STA-1W, is designed to capture seepage from STA-1W to the neighboring area. Seepage through the old ENR supply canal is represented as SEEP1 and seepage in and out of the seepage canal to the north is represented as SEEP2. SEEP3 represents the two seepage possibilities into or out of the discharge canal to the west, regardless of the magnitude. SEEP4 represents the possible seepage loss through the southern levee into the old Knight's Farm or into WCA1. The unmeasured seepage flow from WCA 1 into STA-1W from the east is represented by L-7b.

In computing the water balance for STA-1W, it is essential to identify quantifiable variables from unquantifiable variables, making reasonable assumptions to reduce the quantity of unknowns as much as possible. Since the purpose of the seepage canal is to recirculate seepage and recycled water, it is assumed that the seepage return pump flows are recirculation in the system. Change in storage is represented as follows.

$$\Delta S = G302 + R + L7a + L7b - G251 - G310 - ET - SEEP1 - SEEP2 - SEEP3 - SEEP4 + \varepsilon_T \quad (10)$$



Figure 17. Schematic hydrologic model for STA-1W

where ΔS is change in storage in the system; G-302 is inflow; R is rainfall; L-7a is seepage flow from WCA 1 through the roadside culverts; L-7b is unknown subsurface seepage flow from WCA1 into STA-1W; ET is evapotranspiration losses; SEEP1 is seepage inflow from old ENR supply canal; SEEP2 is seepage to the north from or into the seepage canal; SEEP3 represents the two seepage possibilities into or out of the discharge canal to the west. SEEP4 represents the possible seepage loss or gain through the southern levee of STA-1W. G-310 and G-251 represent outflow pumping; ϵ_T represents total errors in inflow and outflow terms.

Daily change in storage for STA-1W was computed as sum of storage changes in each of the five cells (Cell 1, Cell 2, Cell 3, Cell 4 and Cell 5). Change in storage volume in each cell was computed from the area of the cell and change in stage. Change in stage was computed as the difference between the daily mean stage readings averaged from two or three locations in each cell (**Table 12**). The remainders in the computation of daily water balances are the sum of all errors and unknowns in the system. Daily remainders were computed for the one-year study period based on the following equation:

$REMAINDERS = \Delta S - INFLOWS + OUTFLOWS$ (11)

Discussion

The total inflow through the inflow spillway was 14,636 ha-m (118,651 ac-ft) and was almost equivalent to total outflow through the outflow pump, which was 14,977 ha-m (121,416 ac-ft). Seepage inflow from the L-7 levee through the roadside culverts was a total of 438 ha-m (3,551 ac-ft). The seepage and recirculation pump had a total flow of 6,688 ha-m (54,218 ac-ft). Total average areal rainfall for the study period was 100.8 cm (39.7 inches) and the total average areal evapotranspiration was 137.6 cm (54.2 inches). Rainfall was drier than normal and ET was higher than the five-year ENR average.

For the study period, the mean daily remainders (errors and unknowns) was 0.61 ha-m per day or 4.95 ac-ft per day with the total remainders being 197 ha-m (1,597 ac-ft). The standard deviation of the remainders is 41 ha-m d⁻¹ (323 ac-ft d⁻¹) which signifies high variation. Figure 18 depicts the daily remainders distribution. The positive remainder indicates that there is an overall inflow to the system through unidentified directions. The remainder is 1.1% of the total inflows. Summary of the one-year water budget is shown in Table 14. Details of the water balance terms and calculation results are shown in Appendix III.

The mean hydraulic loading rate for the study period, based on the G-302 spillway inflow, was 1.45 centimeters per day (cm d⁻¹) or 0.57 inches per day (in d⁻¹). The mean hydraulic retention time was computed as the ratio of the mean-estimated water volume of the ENR and the average daily outflow rate. The mean-estimated volume was computed from the area-weighted (by cell) mean depth of 51.9 cm (20.4 inches) and total area of 2,772 ha (6,849 ac). The estimated mean hydraulic retention time was 35.2 days.



Figure 18. Distribution of daily remainders (errors and unknowns) from STA-1W water balance

STA-1W WATER BUDGET SUMMARY

STA-1W has been in operation for one year but the main outflow structure pump station G-310 has been under construction. G-310 pump testing started in July 2000. This water budget study covers the first year of operation of STA-1W (July 1, 1999 to June 30, 2000). For the period of analysis, the total inflow through the inflow spillway (G-302) was 14,636 ha-m or 118,651 ac-ft and the total outflow through the outflow pump (G-251) was 14,977 ha-m (121,416 ac-ft. Seepage inflow from the L-7 levee through the roadside culverts was a total of 438 ha-m (3,551 ac-ft). The seepage and recirculation pump had a total flow of 6,688 ha-m (54,218 ac-ft). Total areal average rainfall for the study period was 100.8 cm (39.7 inches) and the total areal average evapotranspiration was 137.6 cm (54.2 inches). The sum of the errors and unknowns, was 1.1% of the inflows to the system.

The mean hydraulic loading rate for the one-year period, based on the G-302 inflow, was 1.45 cm d^{-1} (0.57 in d^{-1}). The mean hydraulic retention time was computed as the ratio of the mean-estimated volume of STA-1W and the average daily outflow rate. The mean-estimated volume was computed from the area-weighted (by cell) mean depth of 51.9 cm (20.4 inches) and total area of 2772 ha (6849 ac). The estimated mean hydraulic retention time was 35.2 days.

In STA-1W, all hydrologic parameters, with the exception of seepage through the system, are well monitored. Since the direction of seepage is not in one direction, the remainders (errors and unknowns) could not be allocated to one variable.

Table 14. Summary	of water budget	for STA-1W (July 1, 19	99 to June 30, 2000).		
INFLOWS	ha-m	Percent of Total	OUTFLOWS	ha-m	Percent of Total
Spillway Inflow	14,636	81.0%	Outflow Pump	14,977	79.7%
Rain	2,794	15.5%	ET	3,815	20.3%
L-7 Culverts (L-7a)	438	2.4%			
Remainders	197	1.1 %			
Total	18,065	100%	Total	18,792	100%
Change in Storage	727				
Seepage/recirculation Seepage pump (ha-m)	6,688	·			
Loading Rate (cm d ⁻¹)) 1.45				
Average depth (cm)	51.9				
Retention time (days)	35.2				

REFERENCES

Abtew, W. and N. Khanal. 1994. Water Budget Analysis for the Everglades Agricultural Drainage Basin. Water Resources Bulletin Vol. 33(3): 429-439.

Abtew, W., J. Obeysekera and G. Shih. 1995. Spatial Variation of Daily Rainfall and Network Design. Transaction of ASAE. Vol. 38(3): 843-845.

Abtew, W. 1996a. Evapotranspiration Measurements and Modeling for Three Wetland Systems in South Florida. Journal of American Water Resources Association. Vol. 32(3): 465-473.

Abtew, W. 1996b. Lysimeter Study of Evapotranspiration from a Wetland. Evapotranspiration and Irrigation Scheduling. Proceedings of the International Conference. November 3-6, 1996. San Antonio, TX.

Abtew, W. and V. Mullen. 1997. Water Budget Analysis for the Everglades Nutrient Removal Project (August 20, 1996 to August 19, 1997). Technical Memorandum WRE # 354.

Abtew, W. and D. Downey. 1998. Water Budget Analysis for the Everglades Nutrient Removal Project (August 20, 1997 to August 19, 1998). Technical Memorandum WRE # 368.

Choi, J. and J. W. Harvey. 2000. Quantifying Time-Varying Groundwater Discharge and Recharge in Wetlands of the Northern Florida Everglades. The Society of Wetland Scientists. Vol. 20(3): 500-511.

Davis, J.H. 1943. Vegetation of the Everglades and Conservation from the Point of View of the Ecologist. Soil Science Society of Florida Proceedings V-A: 105-115.

Guardo, M. and T. Kosier. 1993. Preliminary Operation Scheme for the ENR Project. South Florida Water Management District, West Palm Beach, FL.

Guardo, M. 1996. Hydrologic Balance of a Subtropical Wetland Constructed for Nutrient Removal. Presented at AWRA 32nd Annual Conference and Symposium on GIS and Water Resources. September 22-26, 1996.

Guardo, M. and A. Prymas. 1998. Calibration of Steady State Seepage Simulations to Estimate Subsurface Seepage into an Artificial Wetland. Engineering Approaches to Ecosystem Restoration. Proceedings of the Conference, ASCE, March 22-27, 1998. Denver, CO.

Hutcheon Engineers. 1996. Everglades Construction Project Stormwater Treatment Area No. 1-W, Detailed Design Report, West Palm Beach, FL.

Jammal and Associates, Inc. 1991. Geotechnical Services SFWMD Everglades Nutrient Removal Project. Draft Report Submitted to the South Florida Water Management District. West Palm Beach, FL.

South Florida Water Management District (SFWMD). 1996. Water Budget Analysis for the Everglades Nutrient Removal Project (August 19, 1994 to August 19, 1996). Technical Memorandum WRE # 347.

South Florida Water Management District (SFWMD). 1998. Operation Plan Stormwater Treatment Area 1 West (STA-1W), Official Draft, West Palm Beach, FL.

Whalen, B.M. and P.J. Whalen. 1994. Nonpoint Source Regulatory Program for the Everglades Agricultural Area. ASAE Paper FL94-101.

APPENDIX I

. .

ENR Water Balance Terms With Calculated Remainders

.

$\begin{array}{c c c c c c c c c c c c c c c c c c c $	ET Remai	ET	Rain	Seepage	Outflow	Seepage	Inflow	Change in	Date
$\begin{array}{c c c c c c c c c c c c c c c c c c c $				L-7a	Բստբ	Pump	Pump	Storage	
ha-mha-mha-mha-mha-mha-mha-mha-mha-mha-mha-m $8/20/98$ 10.5900.00012.11118.3480.78125.4913.8606.52 $8/21/98$ 1.2169.36613.37425.4530.91842.7475.142-21.22 $8/22/98$ 39.72724.82416.31023.8921.0281.5697.24143.42 $8/23/98$ 6.58843.24114.54322.3921.0090.0008.415-6.83 $8/24/98$ -8.04520.71412.17021.1690.9090.0008.9090.44 $8/25/98$ -23.2800.00011.76118.9350.7090.0009.3574.33 $8/26/98$ -28.9580.0008.80319.1060.6090.0007.782-2.65 $8/27/98$ -21.8420.00011.96215.6120.4881.9614.941-3.75 $8/28/98$ -20.6800.0009.00616.5400.3830.0007.7823.25 $8/29/98$ -27.0890.00011.78813.1320.4000.0008.307-6.03 $8/31/98$ -18.2670.0008.76212.8350.4161.5698.6311.22 $9/1/98$ -9.1700.0009.30711.4700.45034.1197.921-24.34 $9/2/98$ 11.4730.00010.85114.2370.52818.4327.72014.46					G-251	G-250_S	G-250		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	1a-m ha-	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	
8/21/981.2169.36613.37425.4530.91842.7475.142-21.2 $8/22/98$ 39.727 24.82416.31023.8921.0281.5697.24143.41 $8/23/98$ 6.58843.24114.54322.3921.0090.0008.415-6.8 $8/24/98$ -8.04520.71412.17021.1690.9090.0008.9090.44 $8/25/98$ -23.2800.00011.76118.9350.7090.0009.3574.30 $8/26/98$ -28.9580.0008.80319.1060.6090.0007.782-2.66 $8/27/98$ -21.8420.00011.96215.6120.4881.9614.941-3.73 $8/28/98$ -20.6800.0009.00616.5400.3830.0007.7823.25 $8/29/98$ -27.0890.00011.78813.1320.4000.0008.307-6.03 $8/30/98$ -18.2670.0008.76212.8350.4161.5698.6311.22 $8/31/98$ -15.3850.00010.71411.0980.4240.0009.1104.39 $9/1/98$ -9.1700.0009.30711.4700.45034.1197.921-24.34 $9/2/98$ 11.4730.00010.85114.2370.52818.4327.72014.46	3.860	l 3.860	25.491	0.781	18.348	12.111	0.000	10.590	8/20/98
8/22/9839.72724.82416.31023.8921.0281.5697.24143.438/23/986.58843.24114.54322.3921.0090.0008.415-6.838/24/98-8.04520.71412.17021.1690.9090.0008.9090.448/25/98-23.2800.00011.76118.9350.7090.0009.3574.308/26/98-28.9580.0008.80319.1060.6090.0007.782-2.658/27/98-21.8420.00011.96215.6120.4881.9614.941-3.738/28/98-20.6800.0009.00616.5400.3830.0007.7823.238/29/98-27.0890.00011.78813.1320.4000.0008.307-6.038/30/98-18.2670.0008.76212.8350.4161.5698.6311.238/31/98-15.3850.00010.71411.0980.4240.0009.1104.399/1/98-9.1700.0009.30711.4700.45034.1197.921-24.349/2/9811.4730.00010.85114.2370.52818.4327.72014.46	5.142 -	7 5.142	4 <u>2</u> .747	0.918	25.453	13.374	9.366	1.216	8/21/98
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	7.241	7.241	1.569	1.028	23.892	16.310	24.824	39.727	8/22/98
8/24/98 -8.045 20.714 12.170 21.169 0.909 0.000 8.909 0.4 8/25/98 -23.280 0.000 11.761 18.935 0.709 0.000 9.357 4.30 8/26/98 -28.958 0.000 8.803 19.106 0.609 0.000 7.782 -2.67 8/27/98 -21.842 0.000 11.962 15.612 0.488 1.961 4.941 -3.77 8/28/98 -20.680 0.000 9.006 16.540 0.383 0.000 7.782 3.25 8/29/98 -27.089 0.000 11.788 13.132 0.400 0.000 8.307 -6.09 8/30/98 -18.267 0.000 8.762 12.835 0.416 1.569 8.631 1.22 8/31/98 -15.385 0.000 10.714 11.098 0.424 0.000 9.110 4.39 9/1/98 -9.170 0.000 9.307 11.470 0.450 34.119 7.921 -24.34 9/2/98 11.473 0.000 10.851 14.237	8.415) 8.415	0.000	1.009	22.392	14.543	43.241	6.588	8/23/98
8/25/98-23.2800.00011.76118.9350.7090.0009.3574.308/26/98-28.9580.0008.80319.1060.6090.0007.782-2.678/27/98-21.8420.00011.96215.6120.4881.9614.941-3.778/28/98-20.6800.0009.00616.5400.3830.0007.7823.258/29/98-27.0890.00011.78813.1320.4000.0008.307-6.058/30/98-18.2670.0008.76212.8350.4161.5698.6311.228/31/98-15.3850.00010.71411.0980.4240.0009.1104.359/1/98-9.1700.0009.30711.4700.45034.1197.921-24.349/2/9811.4730.00010.85114.2370.52818.4327.72014.46	8.909) 8.909	0.000	0.909	21.169	12.170	20.714	-8.045	8/24/98
8/26/98 -28.958 0.000 8.803 19.106 0.609 0.000 7.782 -2.67 8/27/98 -21.842 0.000 11.962 15.612 0.488 1.961 4.941 -3.77 8/28/98 -20.680 0.000 9.006 16.540 0.383 0.000 7.782 3.25 8/29/98 -27.089 0.000 11.788 13.132 0.400 0.000 8.307 -6.05 8/30/98 -18.267 0.000 8.762 12.835 0.416 1.569 8.631 1.25 8/31/98 -15.385 0.000 10.714 11.098 0.424 0.000 9.110 4.39 9/1/98 -9.170 0.000 9.307 11.470 0.450 34.119 7.921 -24.34 9/2/98 11.473 0.000 10.851 14.237 0.528 18.432 7.720 14.44	9.357	9.357	0.000	0.709	18.935	11.761	0.000	-23.280	8/25/98
8/27/98 -21.842 0.000 11.962 15.612 0.488 1.961 4.941 -3.7. 8/28/98 -20.680 0.000 9.006 16.540 0.383 0.000 7.782 3.2. 8/29/98 -27.089 0.000 11.788 13.132 0.400 0.000 8.307 -6.0. 8/30/98 -18.267 0.000 8.762 12.835 0.416 1.569 8.631 1.2. 8/31/98 -15.385 0.000 10.714 11.098 0.424 0.000 9.110 4.39 9/1/98 -9.170 0.000 9.307 11.470 0.450 34.119 7.921 -24.34 9/2/98 11.473 0.000 10.851 14.237 0.528 18.432 7.720 14.46	7.782) 7.782	0.000	0.609	19.106	8.803	0.000	-28.958	8/26/98
8/28/98 -20.680 0.000 9.006 16.540 0.383 0.000 7.782 3.23 8/29/98 -27.089 0.000 11.788 13.132 0.400 0.000 8.307 -6.03 8/30/98 -18.267 0.000 8.762 12.835 0.416 1.569 8.631 1.23 8/31/98 -15.385 0.000 10.714 11.098 0.424 0.000 9.110 4.39 9/1/98 -9.170 0.000 9.307 11.470 0.450 34.119 7.921 -24.34 9/2/98 11.473 0.000 10.851 14.237 0.528 18.432 7.720 14.46	4.941	t 4.941	1.961	0.488	15.612	11.962	0.000	-21.842	8/27/98
8/29/98 -27.089 0.000 11.788 13.132 0.400 0.000 8.307 -6.02 8/30/98 -18.267 0.000 8.762 12.835 0.416 1.569 8.631 1.22 8/31/98 -15.385 0.000 10.714 11.098 0.424 0.000 9.110 4.39 9/1/98 -9.170 0.000 9.307 11.470 0.450 34.119 7.921 -24.34 9/2/98 11.473 0.000 10.851 14.237 0.528 18.432 7.720 14.46	7.782) 7.782	0.000	0.383	16.540	9.006	0.000	-20.680	8/28/98
8/30/98-18.2670.0008.76212.8350.4161.5698.6311.2.8/31/98-15.3850.00010.71411.0980.4240.0009.1104.399/1/98-9.1700.0009.30711.4700.45034.1197.921-24.349/2/9811.4730.00010.85114.2370.52818.4327.72014.40	8.307) 8.307	0.000	0.400	13.132	11.788	0.000	-27.089	8/29/98
8/31/98 -15.385 0.000 10.714 11.098 0.424 0.000 9.110 4.39 9/1/98 -9.170 0.000 9.307 11.470 0.450 34.119 7.921 -24.34 9/2/98 11.473 0.000 10.851 14.237 0.528 18.432 7.720 14.46	8.631	8.631	1.569	0.416	12.835	8.762	0.000	-18.267	8/30/98
9/1/98-9.1700.0009.30711.4700.45034.1197.921-24.349/2/9811.4730.00010.85114.2370.52818.4327.72014.46	9.110	9.110	0.000	0.424	11.098	10.714	0.000	-15.385	8/31/98
9/2/98 11.473 0.000 10.851 14.237 0.528 18.432 7.720 14.40	7. 9 21 ·	9 7. 9 21	34.119	0.450	11.470	9.307	0.000	-9.170	9/1/98
	7.720	2 7.720	18.432	0.528	14.237	10.851	0.000	11.473	9/2/98
9/3/98 -3.545 0.000 11.052 12.968 0.540 0.000 8.832 17.71	8.832) 8.832	0.000	0.540	12.968	11.052	0.000	-3.545	9/3/98
9/4/98 -18.349 0.000 10.276 11.453 0.495 0.000 7.643 0.23	7.643) 7.643	0.000	0.495	11.453	10.276	0.000	-18.349	9/4 /98
9/5/98 -0.989 0.000 12.053 9.799 0.532 16.471 2.270 -5.92	2.270	ı 2.270	16.471	0.532	9.799	12.053	0.000	-0.989	9/5/98
9/6/98 -6.348 0.000 8.899 8.030 0.643 0.000 7.967 9.00	7.967) 7.967	0.000	0.643	8.030	8.899	0.000	-6.348	9/6/98
9/7/98 -10.624 0.000 10.288 10.215 0.653 4.706 2.548 -3.22	2.548	5 2.548	4.706	0.653	10.215	10.288	0.000	-10.624	9/7/98
9/8/98 1.410 0.000 13.552 9.721 0.666 28.629 7.133 -11.03	7.133 ·	7.133	28.629	0.666	9.721	13.552	0.000	1.410	9/8/98
9/9/98 15.465 28.397 12.603 10.516 0.668 0.000 6.454 3.37	6.454) 6.454	0.000	0.668	10.516	12.603	28.397	15.465	9/9/98
9/10/98 69.651 79.618 15.769 12.503 0.654 64.709 3.366 -59.46	3.366	3.366	64.709	0.654	12.503	15.769	79.618	69.651	9/10/98
9/11/98 73,760 79.518 14.098 21.541 0.613 0.000 5.126 20.29	5.126	5.126	0.000	0.613	21.541	14.098	79.518	73,760	9/11/98
9/12/98 26.230 79.751 11.453 22.368 0.581 0.000 5.512 -26.22	5.512 -	5.512	0.000	0.581	22.368	11.453	79.751	26.230	9/12/98
9/13/98 21.948 74.681 11.495 24.046 0.550 0.000 7.180 -22.03	7.180 -	7.180	0.000	0.550	24.046	11.495	74.681	21.948	9/13/98
9/14/98 0.886 39.035 17.526 25.245 0.539 5.883 7.674 -11.65	7.674 ·	3 7.674	5.883	0.539	25.245	17.526	39.035	0.886	9/14/98
9/15/98 0.137 0.683 16.278 26.809 0.557 36.472 2.517 -8.2	2.517	2.517	36.472	0.557	26.809	16.278	0.683	0.137	9/15/98
9/16/98 32.348 46.837 16.207 38.017 0.843 25.099 1.575 -0.83	1.575	9 1.575	25.099	0.843	38.017	16.207	46.837	32.348	9/16/98
9/17/98 30.503 47.637 14.866 43.104 1.091 63.533 2.826 -35.82	2.826	3 2.826	63.533	1.091	43.104	14.866	47.637	30.503	9/17/98
9/18/98 47.080 69.731 17.482 51.058 1.590 38.825 3.057 -8.95	3.057	5 3.057	38.825	1.590	51.058	17.482	69.731	47.080	9/18/98
9/19/98 4.243 3.790 17.357 51.975 2.267 3.137 4.478 51.50	4.478	7 4.478	3.137	2,267	51.975	17.357	3.790	4.243	9/19/98
9/20/98 -26.435 0.000 16.532 45.372 2.485 16.471 3.937 3.91	3.937	l 3.937	16.471	2.485	45.372	16.532	0.000	-26.435	9/20/98
9/21/98 -27.877 0.000 16.545 42.707 2.848 21.178 6.732 -2.40	6.732	6.732	21.178	2.848	42.707	16.545	0.000	-27.877	9/21/98
9/22/98 -24.079 0.000 16.562 36.735 3.287 0.000 6.747 16.11	6.7 47	6.747	0.000	3.287	36.735	16.562	0.000	-24.079	9/2.2/98
9/23/98 -30.549 0.000 14.206 31.024 3.485 0.000 5.759 2.74	5.759) 5.759	0.000	3.485	31.024	14.206	0.000	-30.549	9/23/98
9/24/98 - 29 879 0.000 14.945 28.064 3.486 9.804 5.867 - 9.23	5.867	5.867	9,804	3,486	28.064	14.945	0.000	-29 879	9/24/98
9/25/98 22.487 0.000 15.886 31.609 3.709 54.512 2.347 -1.77	2.347	2.347	54.512	3.709	31.609	15.886	0.000	22.487	9/25/98
9/26/98 2 301 0 000 16 503 29.091 3.934 0.000 4.431 31.85	4.431) 4.431	0.000	3.934	29.091	16 503	0.000	2 301	9/26/98
9/27/98 -30.947 0.000 16.444 25.947 3.911 0.000 6.917 -1.99	6.917) 6.917	0.000	3.911	25 947	16 444	0.000	-30 947	9/27/98
9/28/98 -12 193 32 825 16 278 17 952 3.387 0.000 6.948 -23.50	6.948) 6.948	0.000	3,387	17 952	16.278	32 825	-12 193	9/28/98
9/29/98 24 139 35 088 14 590 8 299 2.884 0.000 6.686 1.15	6.686) 6.686	0.000	2.884	8 299	14 590	35 088	74 139	9/29/98
9/30/98 9 357 49.862 16.143 12.997 2.460 0.000 6.686 -23.28	6.686) 6.686	0.000	2.460	12.997	16 143	49 867	Q 357	9/30/98
10/1/98 39.648 31.687 16.099 12.906 2.153 0.000 6.902 25.61	6.902) 6.902	0.000	2.153	12.906	16.099	31 687	39 648	10/1/98
10/2/98 +0.163 0.000 16.222 15.287 1.946 0.000 7.056 20.23	7.056) 7.056	0.000	1 946	15 287	16 222	000 0	-0 163	10/2/98
10/3/98 -5.414 0.000 16.178 15.519 1.829 0.000 7.226 15.50	7.226) 7.226	0.000	1 829	15 519	16 178	0.000	_5 414	10/3/98
10/4/98 -13.710 0.000 12.950 15.539 1.855 3.137 5.558 2.39	5.558	7 5.558	3.137	1.855	15.539	12.950	0.000	-13.710	10/4/98

$\begin{array}{ c c c c c c c c c c c c c c c c c c c$	
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	ha-m
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	1.982
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	-3.339
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	-25.305
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	0.958
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	13.627
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	13.734
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	-16.447
10/13/9823.77956.89816.11415.2411.7313.9224.66310/14/9833.02379.45515.87418.9111.6310.0003.69010/15/9832.78879.65515.98923.8331.5771.5696.60810/16/9835.35079.52515.97928.7241.5998.6286.31510/17/9823.10879.26615.84730.8871.5210.0006.70110/18/9817.40579.30815.77234.3271.4550.0006.06810/19/9820.11276.79514.68838.2491.46115.2953.15010/20/9821.78365.42015.86040.4051.6062.7455.51210/21/989.60243.38015.69343.7331.69313.7264.47810/22/98-7.93347.74015.85543.6131.7980.7844.030	-5.558
10/14/9833.02379.45515.87418.9111.6310.0003.69010/15/9832.78879.65515.98923.8331.5771.5696.60810/16/9835.35079.52515.97928.7241.5998.6286.31510/17/9823.10879.26615.84730.8871.5210.0006,70110/18/9817.40579.30815.77234.3271.4550.0006.06810/19/9820.11276.79514.68838.2491.46115.2953.15010/20/9821.78365.42015.86040.4051.6062.7455.51210/21/989.60243.38015.69343.7331.69313.7264.47810/22/98-7.93347.74015.85543.6131.7980.7844.030	-18.869
10/15/9832.78879.65515.98923.8331.5771.5696.60810/16/9835.35079.52515.97928.7241.5998.6286.31510/17/9823.10879.26615.84730.8871.5210.0006.70110/18/9817.40579.30815.77234.3271.4550.0006.06810/19/9820.11276.79514.68838.2491.46115.2953.15010/20/9821.78365.42015.86040.4051.6062.7455.51210/21/989.60243.38015.69343.7331.69313.7264.47810/22/98-7.93347.74015.85543.6131.7980.7844.030	-25.463
10/16/9835.35079.52515.97928.7241.5998.6286.31510/17/9823.10879.26615.84730.8871.5210.0006.70110/18/9817.40579.30815.77234.3271.4550.0006.06810/19/9820.11276.79514.68838.2491.46115.2953.15010/20/9821.78365.42015.86040.4051.6062.7455.51210/21/989.60243.38015.69343.7331.69313.7264.47810/22/98-7.93347.74015.85543.6131.7980.7844.030	-19.571
10/17/9823.10879.26615.84730.8871.5210.0006,70110/18/9817.40579.30815.77234.3271.4550.0006.06810/19/9820.11276.79514.68838.2491.46115.2953.15010/20/9821.78365.42015.86040.4051.6062.7455.51210/21/989.60243.38015.69343.7331.69313.7264.47810/22/98-7.93347.74015.85543.6131.7980.7844.030	-19.364
10/18/9817.40579.30815.77234.3271.4550.0006.06810/19/9820.11276.79514.68838.2491.46115.2953.15010/20/9821.78365.42015.86040.4051.6062.7455.51210/21/989.60243.38015.69343.7331.69313.7264.47810/22/98-7.93347.74015.85543.6131.7980.7844.030	-20.091
10/19/9820.11276.79514.68838.2491.46115.2953.15010/20/9821.78365.42015.86040.4051.6062.7455.51210/21/989.60243.38015.69343.7331.69313.7264.47810/22/98-7.93347.74015.85543.6131.7980.7844.030	-22.962
10/20/9821.78365.42015.86040.4051.6062.7455.51210/21/989.60243.38015.69343.7331.69313.7264.47810/22/98-7.93347.74015.85543.6131.7980.7844.030	-32.040
10/21/989.60243.38015.69343.7331.69313.7264.47810/22/98-7.93347.74015.85543.6131.7980.7844.030	-2.071
10/22/98 -7.933 47.740 15.855 43.613 1.798 0.784 4.030	-0.987
	-10.613
10/23/98 -9.772 78.214 15.789 40.953 1.818 0.000 5.775	-43.076
10/24/98 5.934 78.062 15.715 40.204 1.832 0.000 5.126	-28.630
10/25/98 8.750 78.006 14.105 39.737 1.796 0.000 6.037	-25.278
10/26/98 5.171 75.410 15.789 43.366 1.784 0.000 6.068	-22.589
10/27/98 6.094 67.644 15.720 41.078 1.790 0.392 5.775	-16.879
10/28/98 1.581 40.669 15.718 42.575 1.775 0.000 6.083	7.795
10/29/98 -3.297 45.714 15.659 41.516 1.770 0.000 5.605	-3.660
10/30/98 0.965 51.892 13.777 41.924 1.732 0.000 5.620	-5.115
10/31/98 6.811 52.362 12.038 41.080 1.639 0.000 5.991	-0.119
11/1/98 5.127 52.409 14.029 43.035 1.578 0.000 6.330	0.506
11/2/98 7.203 52.342 13.271 43.911 1.567 0.000 4.385	1.590
11/3/98 4.978 52.308 11.052 43.823 1.563 0.000 3.057	-2.012
11/4/98 40.515 28.313 15.679 55.465 1.817 172.165 0.463	-105.853
11/5/98 263.534 31.577 31.609 88.297 3.153 118.829 1.081	199.352
11/6/98 -14.931 51.256 31.249 94.113 3.791 0.000 3.366	27.501
11/7/98 -37.771 51.484 25.500 90.015 4.331 0.000 4.632	1.061
11/8/98 -54.781 44.645 20.927 83.545 4.724 0.000 5.543	15.061
11/9/98 -65.543 1.967 19.031 71.537 5.018 0.000 6.114	5 123
11/10/98 -65.156 0.000 18.686 59.458 5.211 0.000 5.697	-5 211
11/11/98 -51 211 0.000 16 843 52 242 5 381 0.000 6 500	2 149
11/12/98 -39.946 0.000 16.136 46.030 5.337 0.000 6.747	7 494
1/12/98 -37 009 0.000 15 987 40 559 5 131 0.000 6 979	5 308
11/14/98 -37.085 18.781 13.988 35.406 4.749 0.000 4.431	-15 777
11/15/98 5 389 41 352 14 264 32 297 4 274 0 000 6 022	-1 919
11/16/98 13.465 51.638 13.863 33.410 3.823 0.392 3.706	-5 273
11/17/98 18 607 51 858 13 562 35 673 3 452 0 000 3 860	2 820
1/18/98 10.007 51.000 15.002 55.075 5.452 0.000 5.800 11/18/98 10.041 30.000 11.881 37.078 3.131 0.000 4.000	12.030
11/19/98 -21 900 0.000 12 167 38 905 2 934 0 784 2 918	16 205

Date	Change in	Inflow	Seenage	Outflow	Seepage	Rain	ET	Remainders
	Storage	Ритр	Pump	Pump	L-7a			
		G-250	G-250_S	G-251				
	ha-m	ha-m	ba-m	ha-m	ha-m	ha-m	ha-m	ha-m
11/20/98	-30.018	0.000	12.701	34.778	2.979	0.000	4.447	6.228
11/21/98	-21.456	15.987	14.651	38.475	2.956	0.000	5.512	3.587
11/22/98	-16.961	26.995	13.643	28.262	2.908	0.784	4.709	-14.677
11/23/98	13.816	50.735	10.920	27.386	2.814	0.784	4.323	-8.808
11/24/98	22.822	34.47 7	15.263	31.519	2.827	25.884	2.270	-6.576
11/25/98	27.325	18.960	14.538	34.96 1	2.908	0.000	5.620	46.039
11/26/98	-23.643	0.000	14.294	33.723	2.920	2.745	5.311	9.726
11/27/98	-26.898	0.000	14.602	30.533	2.920	0.000	5.589	6.304
11/28/98	-29.627	0.000	12.992	27.283	2.931	0.000	5.450	0.176
11/29/98	-25.067	0.000	12.400	24.673	2.941	0.000	4.261	0.927
11/30/98	-21.078	0.000	12.180	21.176	2.958	0.000	4.323	1.463
12/1/98	-7.951	31.790	12.488	19.505	2.909	11.765	3.93 7	-30.973
12/2/98	27.646	53.113	12.525	20.254	2.768	0.784	4.555	-4.210
12/3/98	23.723	29.676	13.144	22.754	2.676	0.000	4.076	18.202
12/4/98	10.694	44.021	13.210	24.817	2.628	5.883	4.570	-12.451
12/5/98	27.696	21.871	12.327	28.394	2.626	17.256	0.911	15.248
12/6/98	2.736	29.850	12.158	31.472	2.759	0.000	4.416	6.015
12/7/98	16.203	52.560	12.045	29.794	2.680	0.000	4.956	-4.288
12/8/98	12.456	23.921	11.996	32.314	2.590	0.784	2.764	20.238
12/9/98	-25 227	0.000	12.016	32.556	2.609	0.000	4.076	8.797
12/10/98	-27.470	0.000	11.712	29.931	2.621	0.000	4.508	4.348
12/11/98	-28,495	24.736	10.247	26.554	2.610	7.059	1.729	-34.617
12/12/98	20.456	53 096	10 888	26.650	2.602	0.784	1.096	-8.272
12/13/98	25,737	52.431	13.496	26.889	2.598	0.000	3.366	0.964
12/14/98	26.415	52.218	12.123	29.808	2.423	2.353	2.826	2.055
12/15/98	13 466	17 298	12.875	34,491	2.315	0.000	3.613	31.956
12/16/98	-29 727	0.000	13 954	32,487	2.293	0.000	4.508	4,975
12/17/98	-33 736	0.000	12.030	29 138	2.294	0.000	4.740	-2.151
12/18/98	-27.866	0.000	12.713	24,303	2.296	0.000	4.508	-1.351
12/10/08	-23 765	0.000	10 418	21.277	2.322	0.000	3.212	-1.599
12/20/98	-20 845	0.000	8 314	20.401	2.298	0.000	4.725	1.982
12/21/98	-15 392	0.000	14 379	18 840	2.260	0.000	4.478	5.664
12/22/98	-8 668	0.000	15 326	15 896	2:238	0.000	4.231	9.221
12/23/98	-9.338	0.000	14.044	15.368	2.211	0.000	3.783	7.212
12/24/98	-18 570	0.000	15.062	14.455	2.180	0.000	4.092	-2.203
12/25/98	-10.673	0.000	13418	12 461	2 129	0.000	4.246	3.955
12/26/98	-8 662	0.000	11 756	13,440	2.055	2.745	3.289	3.266
12/20/20	-10 188	0.000	12 630	12.440	2 006	0.000	4.277	4.380
12/28/08	7 871	0.000	13 298	13 728	1 998	44 316	2.054	-22.661
12/20/08	22 202	17 700	16 256	16 107	2 026	0 392	4 817	34,109
12/29/90	23.375	76 586	14 105	15 074	1 957	0.000	5 064	-6.099
12/31/02	16 270	20.560	14 265	15 200	1 875	0.000	4 817	7.938
1/1/00	10.217	20.004	12015	18 262	1 784	0.000	4.045	10 272
1/1/97	10.327	20-201	13.079	71 404	1.704	18 040	2,887	-4 210
1/2/00	17.904 75 816	20.370	13.604	21.400	2 142	12 550	2.887	19 604
1/4/00	20.010	74 720	14 102	26 100	2.138	2 353] 158	1.082
1/4/77	2.000	24.230	14,170	20.107	0,10	2.000		1.002

Date	Change in	Inflow	Seepage	Outflow	Seepage	Rain	ET	Remainders
	Storage	Pump	Բստբ	Pump	L-7a			
		G-250	G-250_S	G-251				
	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m
1/5/99	· -0 .70 4	18.482	14.783	26.256	2.053	0.784	3.459	7.691
1/6/99	-12.958	16.031	14.054	25.336	2.010	0.000	4.601	-1.062
1/7/99	-0.482	26.429	12.899	24.274	2.059	0.000	4.030	-0.667
1/8/99	3.863	24.563	14.675	22.649	2.116	0.000	3.165	2.999
1/9/99	0.935	26.574	11.583	22.896	2.016	0.000	4.323	-0.435
1/10/99	8.145	26.571	13.936	24.761	1.890	3.137	1.158	2.465
1/11/99	2.807	26.557	13.851	26.336	1.883	0.000	4.323	5.027
1/12/99	-2.521	26.574	12.407	25.916	1.923	0.000	3.459	-1.643
1/13/99	1.167	26.574	13.300	25.588	1.919	3.922	3.165	-2.494
1/14/99	5.704	26.571	13.491	25.783	1.910	0.392	3.165	5.779
1/15/99	0.622	23.970	9.794	26.106	1.950	0.000	3.165	3.974
1/16 /99	0.609	26.552	14.044	26.207	1.852	0.000	4.323	2.735
1/17/99	-0.361	26.571	11.451	25.534	1.795	0.000	4.045	0.852
1/18/99	-2.081	26.574	11.162	26.116	1.713	0.000	3.752	-0.500
1/19/99	1.306	26.588	12.970	25.896	1.693	0.000	4.339	3.259
1/20 /99	2.011	26.569	12.197	26.410	1.669	0.000	4.045	4.228
1/21/99	-2.149	26.569	13.521	25.575	1.649	0.000	4.617	-0.175
1/22/99	-0.642	22.272	11.730	25.573	1.669	0.000	4.617	5.606
1/23/99	-5.366	26.571	11.830	23.929	1.640	0.000	4.632	-5.016
1/24/99	35.694	26.559	13.895	29.013	1.566	38.825	2.887	0.644
1/25/99	11.275	22.468	13.229	31.648	1.604	0.000	4.617	23.467
1/26/99	-10.405	31.107	13.063	31.949	1.557	0.392	5.203	-6.309
1/27/99	-5.132	35.382	13.924	30.709	1.512	0.000	4.910	-6.408
1/28/99	5.358	31.986	13.210	27.242	1.472	0.000	4.910	4.052
1/29/99	-1.254	37.975	15.940	31.166	1.447	0.000	4.045	-5.465
1/30/99	2.106	43.255	13.958	29.456	1.355	0.000	5.203	-7.845
1/31/99	7.725	41.364	10.085	30.706	1.241	7.451	1.729	-9.896
2/1/99	26.285	61.023	13.396	48.127	1.388	11.373	2.023	2.650
2/2/99	11.248	44.178	15.798	34.159	1.414	0.000	3.474	3.289
2/3/99	7.355	33.892	15.838	35.494	1.372	0.000	4.925	12.512
2/4/99	-7.535	26.549	11.764	35.827	1.295	0.000	5.512	5.960
2/5/99	-14.451	26.557	8.140	35.568	1.257	0.000	4.925	-1.771
2/6/99	-17.132	26.564	5.931	35.208	1.197	0.000	4.925	-4.760
2/7/99	-10.133	26.564	6.711	32.735	1.152	0.000	3.474	-1.640
2/8/99	-10.707	26.566	9.980	31.585	1.149	0.000	3.474	-3.364
2/9/99	-13.655	26.566	11.781	30.540	1.144	0.000	3.474	-7.351
2/10/99	-5.567	25.739	8.620	29.659	1.269	0.000	3.181	0.264
2/11/99	-9.180	25.761	5.669	29.326	1.286	0.392	4.339	-2.954
2/12/99	6.501	25.458	6.755	23.339	1.278	5.098	3.474	1.481
2/13/99	34.213	0.000	6.518	10.467	1.252	0.000	2.903	46.331
2/1 4/99	-18.084	0.000	7.144	17.195	1.195	0.000	4.632	2.549
2/15/99	-22.499	0.000	4.913	17.164	1.199	0.000	3.181	-3.354
2/16/99	-31.677	16.706	4.583	27.775	1.260	0.000	2.887	-18.982
2/17/99	-39.968	21.441	4.881	24.081	1.261	0.000	3.752	-34.837
2/18/99	1.328	26.586	4.734	19.784	1.287	5.490	4.910	-7.341
2/19/99	5.812	26.510	4.727	J8.549	1.308	0.000	4.632	1.174

Dat	e	Change in Storage	Inflow Pump	Seepage Pump	Outflow Pump	Seepage L-7a	Rain	ET	Remainders
		····-	G-250	G-250 S	G-251	·			
		ha-m	ba-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m
2/20	/99	1.478	26.584	6.665	19.427	1.161	0.000	5.497	-1.342
2/21	/99	2.857	26.584	6.944	20.875	1.050	0.000	4.910	1.009
2/22	/99	-3.649	26.586	3.966	21.783	1.013	0.000	5.775	-3.691
2/23	/99	-4.379	22.608	3.614	21.250	1.023	0.000	3.181	-3.579
2/24	/99	-16.529	0.000	5.109	20.545	0.949	0.000	5.775	8.842
2/25	/99	-21.659	0.000	3.068	17.998	0.955	0.000	5.188	0.572
2/26	/99	-21.720	0.000	0.793	16.503	0.938	0.000	5.775	-0.380
2/27	/99	-30.381	0.000	0.000	14.237	0.941	0.000	5.775	-11.310
2/28	/99	-18. 18 7	0.000	0.000	11.725	0.936	0.000	5.188	-2.211
3/1	/99	-17.000	0.000	0.000	9.733	0.889	0.000	6.052	-2.103
3/2	2/99	-16.328	0.000	0.000	9.165	0.890	0.000	6.037	-2.015
3/3	3/99	-6.847	0.000	0.000	8.192	0.890	8.236	2.007	-5.775
3/4	/99	8.938	0.000	0.000	1.603	0.820	0.000	6.902	16.622
3/5	5/99	2.827	0.000	0.000	0.000	0.801	0.000	6.624	8.649
3/6	5/99	-3.788	0.000	0.000	0.000	0.775	0.000	5.188	0.624
3/7	/99	-4.997	0.000	0.000	0.000	0.709	0.000	6.052	0.346
3/8	1/99	-31.448	1.258	0.000	16.229	0.666	0.000	5.759	-11.384
3/9	9/99	-30.306	0.000	0.000	6.567	0.656	0.000	6.330	-18.065
3/10	//99	-12.216	0.000	0.000	5,723	0.548	0.000	5.188	-1.854
3/11	/99	-10.326	0.000	0.000	4.194	0.502	0.000	6.624	-0.010
3/12	/00	-10.445	0.000	0.000	10.306	0.497	0.000	6.330	5.694
3/12	1/00	-13.056	0.000	0.000	3.545	0.514	0.000	4.894	-5.130
3/12	1/99	-9 788	0.000	0.000	3.044	0.540	1.961	4.617	-4.628
3/14	./00	-5 454	0.000	0.000	3.513	0.409	0.000	3.459	1.108
3/16	5/99	-5.094	0.000	0.000	2.439	0.378	0.392	6.624	3.199
3/12	7/99	-9.244	0.000	0.000	2.924	0.378	0.000	6.330	-0.367
3/15	2/99	-6 263	0.000	0.000	2,408	0.338	0.000	5.759	1.566
3/10	00/00	-7 760	0.000	0.000	3.098	0.277	0.000	7.195	2.255
3/20	7/00 1/00	-7.800	0.000	0,000	2.200	0.229	0.000	4.894	-0.934
3/21	./00	-7.565	0.000	0.000	2.107	0.165	0.000	6.052	0.430
3/21	7/00	-9.095	0.000	- 0.000	2,425	0.088	0.000	7.488	0.730
3/44	2/22	-9.075	6 792	0.000	1 588	0.071	0.000	5.759	-1.142
3/22	1/00	8 437	20.814	0.000	2.148	0.035	0.000	6.639	-3.624
3/24	7/22 5/00	74 748	35 438	0.000	1 006	0.010	0.000	6.655	-3.541
3/2.	4777 5700	27.240	35 827	0.000	2.400	0.000	14.903	5.203	-20.321
3/21	7/00	31 643	35 255	0.000	2.846	0.000	0.000	7.519	6.753
3/25	R/00	22 143	35 299	0.000	4.470	0.000	0.000	6.068	-2.617
3/20	3/00	18 666	35 338	0.000	5.718	0.000	0.000	4.910	-6.044
2/2/	7777 1700	17 847	35 216	0.000	13.457	0.000	0.000	5.775	1.858
3/3	1/00	15 266	35 098	0.000	7 568	0.000	0.000	4.339	-7.926
313. Al:	1/00	16 043	35.098	0.000	9.665	0.000	0.784	6.068	-3.207
	1/77 7/00	10.743	25.020	0.000	10 717	0.000	0.000	6.655	-1.095
ч/л Л /*	u 77 2/00	15.027	25 101	0.000 0 (1/1/1)	12 089	0.000	0.000	7.519	-0.104
ч/. Л.С	1/27 4/00	10,477 0 ///	24 102	0.000	14 235	0.000	0.000	6.933	-3.581
ч), Л / 4	+/ソソ 5/00	7.444 17 386	AR 440	0.000	14 200	0,000	0.000	7.210	-9.453
ч/. ДИ	5/00	20.844	49 847	0.000	15,730	0.000	0.000	5.775	-7.499
	~ ~ ~			0,000					

Date	Change in Storage	Inflow Pump G-250	Seepage Pump G-250_S	Outflow Pump G-251	Seepage L-7a	Rain	ET	Remainders
	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m
4/7/99	16.028	49.634	0.000	17. 646	0.000	0.000	7.519	-8.441
4/8/99	25.203	46.128	0.000	18.018	0.000	0.000	7.226	4.319
4/9/99	13.049	46.390	0.000	21.355	0.000	0.000	7.226	-4.760
4/10/99	11.276	49.460	0.000	24.893	0.000	0.000	7.813	-5.479
4 /11/99	14.067	49.940	0.000	26.554	0.000	0.000	7.241	-2.078
4/12/99	12.845	49.539	0.000	29.089	0.000	0.000	5.790	-1.814
4/13/99	5.460	42.526	0.000	29.551	0.000	0.000	7.813	0.298
4/]4/99	1.409	38.477	0.000	28.406	0.000	0.000	7.241	-1.421
4/15/99	-3.095	34.056	0.000	20.012	0.000	0.000	7.241	-9.898
4/16/99	37.004	36 . 794	0.000	13.946	0.000	0.000	6.377	20.533
4/17/99	11.893	41.264	0.000	19.730	0.000	0.392	3.181	-6.852
4/18/99	12.099	42.142	0.000	19.645	0.000	0.392	4.925	-5.865
4/19/99	3.430	46.700	0.000	27.029	0.000	0.000	7.226	-9.016
4/20/99	5.476	38.912	0.000	23.474	0.000	0.000	.8.106	-1.857
4/21/99	-6.197	34.648	0.000	34.533	0.000	0.000	8.399	2.087
4/22/99	-31.574	38.364	0.000	37.789	0.000	0.000	6.670	-25.479
4/23/99	-13.537	40.933	0.000	32.438	0.000	0.000	6.686	-15.346
4/24/99	2.566	42.575	0.000	30.454	0.000	0.000	7.859	-1.696
4/25/99	0.450	41.455	0.000	29.953	0.000	0.000	6.408	-4.644
4/26/99	-0.780	38.697	0.000	44.173	0.000	0.000	7.272	11.968
4/27/99	15.120	37.317	0.000	30.630	0.000	36.080	4.076	-23.571
4/28/99	25.712	41.183	0.000	35.605	0.000	7.059	3.196	16.270
4/29/99	2.718	42.517	0.000	36.221	0.000	0.392	6.114	2.144
4/30/99	5.083	49.294	0.000	34.073	0.000	0.392	7.288	-3.243
5/1/99	2.115	49.428	0.000	36.821	0.000	0.000	6.979	-3.514
5/2/99	0.593	49.394	0.000	36.950	0.000	0.000	9.017	-2.834
5/3/99	1.266	42.245	0.000	36.463	0.000	0.000	6.979	2.464
5/4/99	-3.653	39.353	0.000	35.940	0.000	0.000	8.152	1.087
5/5/99	-7.310	38.245	0.000	32.646	0.000	0.000	6.114	-6.794
5/6/99	-5.658	37.041	0.000	30.674	0.000	0.000	8.446	-3.579
5/7/99	-5.587	33.933	0.000	29.204	0.000	0.000	8.461	-1.855
5/8/99	-4.923	44.863	0.000	30.643	0.000	0.000	6.130	-13.013
5/9/99	-1.043	22.172	0.000	31.514	0.000	7.059	6.099	7.338
5/10/99	-15.957	18.270	0.000	30.922	0.000	0.392	8.415	4.718
5/11/99	13.735	35.908	0.000	28.252	0.000	44.316	5.234	-33.002
5/12/99	10.913	6.215	0.000	32.394	0.000	9.020	3.489	31.563
5/13/99	-29.551	0.024	0.000	27.878	0.000	0.000	8.415	6.717
5/14/99	-34.001	0.000	0.000	23.307	0.000	0.000	7.550	-3.143
5/15/99	-19.086	0.000	0.000	21 286	0.000	21 178	2.903	-16.074
5/16/99	-13.923	0.000	0.000	20.183	0.000	0.000	6.099	12.358
5/17/99	-29.344	0.037	0.000	17.514	0.000	0.000	6.963	-4.903
5/18/99	-28.911	0.000	0.000	14.680	0.000	1.961	6.670	-9.521
5/19/99	-19.985	0.000	0.000	11.265	0.000	0.784	7.257	-2.248
5/20/99	-18 684	0.000	0.000	10 783	0.000	0.000	4.354	-3 54 8
5/21/99	-15.843	0.000	0.000	9 192	0.000	0 392	6 670	-0373
5/77/00	-6.970	0.000	0.000	7 135	0.000	18 432	6 670	-11 508

Date	Change in	Inflow	Secpage	Outflow	Seepage	Rain	ET	Remainders
	Storage	Pump	Pump	Pump	L-7a			
	ha-m	G-250 ha-m	G-250_S ha•m	G-251 ha-m	ha-m	ha-m	ha-m	ha-m
5/23/99	-6.644	0.000	0.000	8.683	0.000	0.000	8. 9 86	11.025
5/24/99	-14.023	0.000	0.000	7.418	0.000	0.000	6.670	0.065
5/25/99	-14.939	0.000	0.000	6.401	0.000	0.000	7.828	-0.710
5/26/99	1.549	25,448	0.000	5.439	0.000	0.000	8.121	-10.338
5/27/99	22.608	41.477	0.000	5.591	0.000	0.000	8.708	-4.570
5/28/99	15.585	38.357	0.000	6.190	0.000	0.000	8.121	-8.460
5/29/99	19.910	47.943	0.000	8.094	0.000	0.784	5.219	-15.506
5/30/99	24.103	44,290	0.000	11.470	0.000	0.000	4.647	-4.070
5/31/99	22.478	43.860	0.000	14.661	0.000	0.000	6.670	-0.051
6/1/99	27.839	42.392	0.000	19.053	0.000	25.884	3.767	-17.617
6/2/99	27.064	11.984	0.000	20.440	0.000	8.236	3.721	31.005
6/3/99	-16.678	0.122	0.000	21.551	0.000	0.392	5.512	9.870
6/4/99	-25.903	0.000	0.000	18.585	0.000	0.000	7.519	0.201
6/5/99	-31.060	0.000	0.000	14.697	0.000	0.000	7.241	-9.121
6/6/99	-19.181	0.000	0.000	11.984	0.000	0.392	8.106	0.517
6/7/99	55.357	19.057	0.000	21.081	0.000	167.851	1.158	-109.313
6/8/99	142.468	38.440	0.000	37.924	0.496	51.375	2.023	92.102
6/9/99	2 0.996	47.750	0.000	36.441	0.960	0.000	6.361	15.088
6/10/99	-4.056	23.302	0.000	35.450	1.307	7.844	5.790	4.732
6/11/99	5.816	17.171	0.000	37.770	1.514	38.433	5.790	-7.742
6/12/99	26.710	17.073	0.000	39.739	1.567	23.138	4.061	28.732
6/13/99	-6.612	17.178	0.000	37.914	1.540	0.000	7.535	20.119
6/14/99	-25.037	21.636	0.000	35.455	1.384	3.137	7.257	-8.483
6/15/99	-4.080	37.520	0.000	32.783	1.211	0.000	5.188	-4.841
6/16/99	-9.175	31.196	0.000	34.056	1.162	13.334	3.736	-17.075
6/17/99	2.764	17.230	0.000	33.116	1.282	10.589	5.342	12.121
6/18/99	-0.337	0.000	0.000	33.483	1.690	23.138	2. 96 4	11.283
6/19/99	-14.684	0.000	0.000	34.039	1.964	7.059	3.165	13.496
6/20/99	-28.724	0.000	0.000	30.731	1.922	0.000	5.389	5.473
6/21/99	-36.123	0.000	0.000	25.938	1.814	1.177	8.893	-4.282
6/22/99	-25.235	0.000	0.000	21.719	1.817	1.961	7.164	-0.129
6/23/99	5.279	11.277	0.000	25.688	1.756	50.983	6.408	-26.642
6/24/99	35.890	29.424	0.000	27.149	1.910	10.589	6.207	27.323
6/25/99	7.967	21.032	0.000	24.631	1.981	9.020	5.126	5.691
6/26/99	30.473	26.385	0.000	27.048	1.894	2.353	5.713	32.602
6/27/99	27.757	17.012	0.000	28.548	2.001	10.589	6.006	32.709
6/2.8/99	25.207	25.098	0.000	31.996	1.831	0.000	5.111	35.384
6/29/99	21.767	31.252	0.000	33.7 9 4	1.706	7.451	5.219	20.371
6/30/99	14.871	32.901	0.000	37.146	1.673	0.784	4.431	21.090

APPENDIX II

λ.

STA-1W Cell 5 Average Stage

STA 1 West, Cell 5 Average Stage

(Cell 5 average stage is computed from manual readings available at G-304, Tailwater, G-305, Head and Tailwater, and G-306, Headwater. Sources of manual readings are from OMD archive data and hardcopies from construction site)

Date	Stage (ft)						
04/15/99	10.74	05/21/99	12.15	06/26/99	12.83	08/01/99	11.49
04/16/99	10.80	05/22/99	12.15	06/27/99	12.75	08/02/99	11.47
04/17/99	10.60	05/23/99	12.15	06/28/99	12.69	08/03/99	11.45
04/18/99	10.69	05/24/99	12.15	06/29/99	12.61	08/04/99	11.42
04/19/99	10.78	05/25/99	12.15	06/30/99	12.58	08/05/99	11.40
04/20/99	10.88	05/26/99	12.12	07/01/99	12.51	08/06/99	11.38
04/21/99	11.00	05/27/99	12.10	07/02/99	12.50	08/07/99	11.35
04/22/99	11.15	05/28/99	12.08	07/03/99	12.46	08/08/99	11.32
04/23/99	11.21	05/29/99	12.06	07/04/99	12.38	08/09/99	11.29
04/24/99	11.30	05/30/99	12.03	07/05/99	12.29	08/10/99	11.24
04/25/99	11.43	05/31/99	12.00	07/06/99	12.25	08/11/99	11.21
04/26/99	11.57	06/01/99	11.97	07/07/99	12.23	08/12/99	11.21
04/27/99	11.70	06/02/99	12.05	07/08/99	12.17	08/13/99	11.18
04/28/99	11.91	06/03/99	12.07	07/09/99	12.16	08/14/99	11.17
04/29/99	12.08	06/04/99	12.08	07/10/99	12.13	08/15/99	11.17
04/30/99	12.14	06/05/99	12.10	07/11/99	12.11	08/16/99	11.16
05/01/99	12.15	06/06/99	12.12	07/12/99	12.09	08/17/99	11.12
05/02/99	12.15	06/07/99	12.14	07/13/99	12.03	08/18/99	11.09
05/03/99	12.17	06/08/99	12.52	07/14/99	12.00	08/19/99	11.06
05/04/99	12.22	06/09/99	12.59	07/15/99	12.00	08/20/99	11.06
05/05/99	12.24	06/10/99	12.61	07/16/99	11.99	08/21/99	11.05
05/06/99	12.25	06/11/99	12.59	07/17/99	11.97	08/22/99	11.04
05/07/99	12.24	06/12/99	12.63	07/18/99	11.95	08/23/99	11.03
05/08/99	12.22	06/13/99	12.68	07/19/99	11.94	08/24/99	10.94
05/09/99	12.20	06/14/99	12.72	07/20/99	11.92	08/25/99	10.94
05/10/99	12.18	06/15/99	12.69	07/21/99	11.90	08/26/99	10.90
05/11/99	12.18	06/16/99	12.72	07/22/99	11.93	08/27/99	10.87
05/12/99	12.23	06/17/99	12.75	07/23/99	11.93	08/28/99	10.85
05/13/99	12.27	06/18/99	12.76	07/24/99	11.91	08/29/99	10.82
05/14/99	12.27	06/19/99	12.76	07/25/99	11.88	08/30/99	10.77
05/15/99	12.23	06/20/99	12.77	07/26/99	11.85	08/31/99	10.73
05/16/99	12.20	06/21/99	12.78	07/27/99	11.83	09/01/99	10.69
05/17/99	12.18	06/22/99	12.81	07/28/99	11.79	09/02/99	10.66
05/18/99	12.18	06/23/99	12.79	07/29/99	11.78	09/03/99	10.64
05/19/99	12.18	06/24/99	12.89	07/30/99	11.77	09/04/99	10.62
05/20/99	12.18	06/25/99	12.90	07/31/99	11.51	09/05/99	10.61

Date	Stage (ft)	Date	Stage (ft)	Date	Stage (ft)	Date	Stage (ft)
09/06/99	10.59	10/19/99	11.05	12/01/99	10.68	01/13/00	10.37
09/07/99	10.58	10/20/99	11.06	12/02/99	10.64	01/14/00	10.36
09/08/99	10.58	10/21/99	11.11	12/03/99	10.61	01/15/00	10.35
09/09/99	10.61	10/22/99	11.09	12/04/99	10.60	01/16/00	10.34
09/10/99	10.62	10/23/99	11.07	12/05/99	10.60	01/17/00	10.34
09/11/99	10.60	10/24/99	11.05	12/06/99	10.59	01/18/00	10.35
09/12/99	10.58	10/25/99	11.04	12/07/99	10.59	01/19/00	10.34
09/13/99	10.56	10/26/99	11.06	12/08/99	10.61	01/20/00	10.35
09/14/99	10.56	10/27/99	11.07	12/09/99	10.61	01/21/00	10.43
09/15/99	10.55	10/28/99	11.05	12/10/99	10.64	01/22/00	10.46
09/16/99	10.54	10/29/99	11.05	12/11/99	10.64	01/23/00	10.47
09/17/99	10.52	10/30/99	11.07	12/12/99	10.64	01/24/00	10.50
09/18/99	10.53	10/31/99	11.10	12/13/99	10.62	01/25/00	10.59
09/19/99	10.53	11/01/99	11.12	12/14/99	10.54	01/26/00	10.63
09/20/99	10.54	11/02/99	11.13	12/15/99	10.55	01/27/00	10.66
09/21/99	10.56	11/03/99	11.11	12/16/99	10.55	01/28/00	10.72
09/22/99	10.57	11/04/99	11.02	12/17/99	10.55	01/29/00	10.76
09/23/99	10.55	11/05/99	10.97	12/18/99	10.54	01/30/00	10.78
09/24/99	10.53	11/06/99	10.97	12/19/99	10.53	01/31/00	10.86
09/25/99	10.54	11/07/99	10.97	12/20/99	10.53	02/01/00	10.91
09/26/99	10.55	11/08/99	10.95	12/21/99	10.52	02/02/00	10.90
09/27/99	10.55	11/09/99	10.91	12/22/99	10.52	02/03/00	10.89
09/28/99	10.52	11/10/99	10.90	12/23/99	10.51	02/04/00	10.89
09/29/99	10.52	11/11/99	10.89	12/24/99	10.50	02/05/00	10.85
09/30/99	10.51	11/12/99	10.88	12/25/99	10.50	02/06/00	10.79
10/01/99	10.49	11/13/99	10.88	12/26/99	10.49	02/07/00	10.74
10/02/99	10.48	11/14/99	10.88	12/27/99	10.49	02/08/00	10.71
10/03/99	10.47	11/15/99	10.88	12/28/99	10.48	02/09/00	10.71
10/04/99	10.47	11/16/99	10.87	12/29/99	10.48	02/10/00	10.72
10/05/99	10.50	11/17/99	10.81	12/30/99	10.47	02/11/00	10.73
10/06/99	10.50	11/18/99	10.79	12/31/99	10.46	02/12/00	10.69
10/07/99	10.52	11/19/99	10.79	01/01/00	10.46	02/13/00	10.65
10/08/99	10.52	11/20/99	10.77	01/02/00	10.45	02/14/00	10.61
10/09/99	10.53	11/21/99	10.78	01/03/00	10.45	02/15/00	10.58
10/10/99	10.54	11/22/99	10.79	01/04/00	10.44	02/16/00	10.54
10/11/99	10.55	11/23/99	10.79	01/05/00	10.40	02/17/00	10.50
10/12/99	10.55	11/24/99	10.78	01/06/00	10.36	02/18/00	10.46
10/13/99	10.54	11/25/99	10.76	01/07/00	10.36	02/19/00	10.42
10/14/99	10.56	11/26/99	10.74	01/08/00	10.36	02/20/00	10.37
10/15/99	10.60	11/27/99	10.72	01/09/00	10.36	02/21/00	10.33
10/16/99	10.76	11/28/99	10.71	01/10/00	10.36	02/22/00	10.28
10/17/99	10.93	11/29/99	10.69	01/11/00	10.3 7	02/23/00	10.22
10/18/99	11.05	11/30/99	10.69	01/12/00	10.38	02/24/00	10.18

Date	Stage (ft)						
02/25/00	10.15	03/27/00	11.02	04/28/00	11.45	05/30/00	11.10
02/26/00	10.12	03/28/00	10.97	04/29/00	11.50	05/31/00	11.07
02/27/00	10.10	03/29/00	10.91	04/30/00	11.56	06/01/00	11.03
02/28/00	10.07	03/30/00	10.93	05/01/00	11.61	06/02/00	11.01
02/29/00	10.08	03/31/00	11.04	05/02/00	11.64	06/03/00	11.00
03/01/00	10.09	04/01/00	11.00	05/03/00	11.64	06/04/00	10.99
03/02/00	10.19	04/02/00	10.94	05/04/00	11.63	06/05/00	10.97
03/03/00	10.18	04/03/00	10.90	05/05/00	11.60	06/06/00	10.98
03/04/00	10.22	04/04/00	10.92	05/06/00	11.55	06/07/00	11.03
03/05/00	10.27	04/05/00	10.85	05/07/00	11.50	06/08/00	11.11
03/06/00	10.33	04/06/00	10.85	05/08/00	11.45	06/09/00	11.21
03/07/00	10.42	04/07/00	10.93	05/09/00	11.41	06/10/00	11.26
03/08/00	10.52	04/08/00	10.97	05/10/00	11.39	06/11/00	11.30
03/09/00	10.67	04/09/00	10.99	05/11/00	11.37	06/12/00	11.33
03/10/00	10.76	04/10/00	11.01	05/12/00	11.35	06/13/00	11.35
03/11/00	10.76	04/11/00	11.03	05/13/00	11.30	06/14/00	11.33
03/12/00	10.75	04/12/00	11.07	05/14/00	11.24	06/15/00	11.28
03/13/00	10.75	04/13/00	11.14	05/15/00	11.20	06/16/00	11.24
03/14/00	10.81	04/14/00	11.28	05/16/00	11.18	06/17/00	11.20
03/15/00	10.86	04/15/00	11.33	05/17/00	11.19	06/18/00	11.17
03/16/00	11.04	04/16/00	11.38	05/18/00	11.22	06/19/00	11.13
03/17/00	11.15	04/17/00	11.39	05/19/00	11.20	06/20/00	11.13
03/18/00	11.21	04/18/00	11.30	05/20/00	11.20	06/21/00	11.18
03/19/00	11.29	04/19/00	11.24	05/21/00	11.20	06/22/00	11.24
03/20/00	11.36	04/20/00	11.24	05/22/00	11.21	06/23/00	11.28
03/21/00	11.33	04/21/00	11.30	05/23/00	11.23	06/24/00	11.30
03/22/00	11.30	04/22/00	11.33	05/24/00	11.23	06/25/00	11.31
03/23/00	11.31	04/23/00	11.36	05/25/00	11.24	06/26/00	11.35
03/24/00	11.25	04/24/00	11.38	05/26/00	11.24	06/27/00	11.42
03/25/00	11.17	04/25/00	11.35	05/27/00	11.21	06/28/00	11.46
03/26/00	11.10	04/26/00	11.34	05/28/00	11.17	06/29/00	11.48
	·	04/27/00	11.39	05/29/00	11.14	06/30/00	11.45

.

-

.

.

APPENDIX III

.

STA-1W Water Balance Terms With Calculated Remainders

.

. .

·

Date	Change in	Inflow	Scepage	Outflow	Secpage	Rain	ET	Remainders
	Storage	Spillway	Pump	Pump	L-7a			
		G302_S	G250S	G251	ham	ha m	ha.m	bo-m
7/1/00	ha-m	ha-m	na-m	0.000	1 699	0.019	6 708	_16 351
7/1/99	-19.153	0.000	21.182	0.000	1.026	0.000	6.764	-10.551
7/2/99	-10.351	0.000	0.000	26.000	1.920	0.000	7 / 20	4 030
7//3/99	-33.090	0.000	0.000	30.003	2.020	2.772	9.216	.11 523
7/4/99	-30.364	0.000	0.000	34.741	1.990	2-210	12 527	-20 861
7/5/99	-39.542	0.000	0.000	35.335	1.907	28.274	15,547	-20.801
7/6/99	-22.336	0.000	0.000	-32.310	1.098	0.000	12,171	22.041 9.502
7/7/99	-32.859	0.000	0.000	29.953	1.239	0.000	10.040	0.303 4 344
7/8/99	-40.387	0.000	0.000	26.564	1.471	0.000	10.949	-4.344
7/9/99	-20.997	0.000	0.000	24.440	1.267	0.000	11.973	14.152
7/10/99	-24.789	0.000	0.000	24.068	1.077	0.000	12.502	10.705
7/11/99	-11.967	0.000	0.000	22.772	0.891	33.818	9.309	-14.330
7/12/99	-5.273	0.000	0.000	22.730	0.781	0.000	13.915	30.391
7/13/99	-35.359	3.951	0.000	21.715	0.705	0.000	14.054	-4.240
7/14/99	-28.409	6.919	0.000	19.116	0.654	0.000	12.141	-4.725
7/15/99	-17.006	0.000	10.792	17.377	0.629	0.000	12.502	12.243
7/16/99	-12.552	0.000	13.224	16.457	0.592	1.386	12.502	14.429
7/17/99	-23.677	0.000	8.710	16.055	0.550	6.376	13.694	-0.854
7/18/99	-24.502	0.000	7.144	14.169	0.492	0.000	14.581	3.735
7/19/99	-22.313	0.000	0.037	13.207	0.508	0.000	13.028	3.415
7/20/99	-20.907	0.000	5.167	11.607	0.412	2.218	10.949	-0.980
7/21/99	-7.075	0.000	5.997	12.557	0.348	60.430	13.555	-41.741
7/22/99	26.127	0.000	3.225	14.807	0.332	25.225	10.949	26.327
7/23/99	-0.055	0.000	6.361	13.988	0.462	1.386	13.472	25.557
7/24/99	-18.199	0.000	2.956	16.461	0.468	0.000]4.747	12.542
7/25/99	-29.145	0.000	5.586	15.197	0.465	0.000	14.581	0.168
7/26/99	-20.539	0.000	. 3.792	11.982	0.472	0.000	11.448	2.418
7/27/99	-15.610	0.000	3.832	8.882	0.475	8.316	12.391	-3.129
7/28/99	-23.384	0.000	3.171	8.133	0.501	0.000	10.922	-4.830
7/29/99	-12.448	0.000	3.364	7.367	0.483	0.000	14.470	8.906
7/30/99	-19.001	0.000	0.000	6.445	0.489	2.772	13.555	-2.262
7/31/99	-111.367	0.000	0.000	6.858	0.476	0.000	14.054	-90.931
8/1/99	-14.251	0.000	5.968	4.871	0.482	0.000	16.105	6.243
8/2 /99	-17.103	0.000	3.014	6.141	0.471	0.832	9.702	-2.563
8/3/99	-15.384	0.000	5.579	5.224	0.462	0.000	11.559	0.937
8/4/99	-5.945	0.000	12.314	5.486	0.470	37.422	10.007	-28.344
8/5/99	14.180	0.000	17.719	7.433	0.484	11.365	10.312	20.076
8/6/99	8.256	0.000	22.811	7.573	0.487	10.534	11.033	15.840
8/7/99	4.161	0.000	21.455	8.823	0.458	16.078	11.337	7.786
8/8/99	-1.907	0.000	20.068	10.594	0.445	Q.000	13.472	21.714
8/9/99	-8.297	0.000	19.950	9.939	0.424	4.158	8.732	5.791
8/10/99	-10.363	0.000	20.092	j1.066	0.420	4.990	11.448	6.742
8/11/99	-8.806	0.000	19.603	11.267	0.398	4.990	14.220	11.294
8/12/99	4.321	0.000	19.363	11.663	0.407	2.218	11.199	24.559
8/13/99	10.970	0.000	20.594	21.526	0.417	59.875	7.124	-20.671
8/14/99	69.902	0.000	20.650	11.438	0.454	58.489	4.103	26.499
8/15/99	1.631	0.000	20.753	28.597	0.456	0.000	12.696	42.468

Date	Change in	Inflow	Seepage	Outflow	Seepage	Rain	ET	Remainders
	Storage	Spillway	Pump	Pump	L-7a			
		G302_S	G250S	G251				•
	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m
8/16/99	-19.031	0.000	20.410	21.800	0.440	0.000	12.225	14.554
8/17/99	-23.533	0.000	20.058	1 9 .747	0.521	5.544	9.536	-0.315
8/18/99	-9.031	0.000	19.955	20.570	0.537	16.909	4.213	-1.694
8/19/99	-8.287	0.000	19.848	18.911	0.621	9.979	6.764	6.787
8/20/99	-2.528	0.000	17.127	17.898	0.744	6.376	12.114	20.364
8/21/99	-7. 977	0.000	17.594	18.962	0.837	0.832	8.427	17.743
8/22/99	-4.221	0.000	16.665	16.222	0.867	0.000	9.619	20.752
8/23/99	-6.076	0.000	18.549	16.153	0.894	0.832	8.177	16.529
8/24/99	-18.987	0.000	24.903	23.540	0.977	70.409	5.766	-61.067
8/25/99	6.481	0.000	27.178	22.686	1.218	0.000	13.999	41.9 47
8/26/99	7.536	0.000	28.428	23.838	1.325	60.430	13.472	-16.908
8/27/99	4.612	0.000	31.183	25.918	1.301	0.000	14.470	43.699
8/28/99	-14.196	0.000	30.310	22.921	1.246	5.544	13,500	15.434
8/29/99	-12.625	0.000	27.719	20.012	1.158	0.000	14.636	20.866
8/30/99	-22.852	0.000	29.275	19.429	1.100	0.000	14.913	10.391
8/31/99	-13.638	0.000	29.145	19.261	1.048	14.137	7.872	-1.690
9/1/99	25.675	89.381	27.915	21.852	0.929	18.295	13.971	-47.107
9/2/99	53.243	41.090	19.860	27.976	0.989	0.000	12.197	51,336
9/3/99	56.862	119,989	17.046	31.763	0.881	0.000	15.856	-16.390
9/4/99	13.413	0.000	14 790	41,895	0.894	0.000	14.802	69.216
9/5/99	-22.049	44 687	10.489	40.956	0.857	0.000	13 555	-13 083
0/6/00	-29.045	0.000	11 867	39.458	0.853	0.000	10 949	19.678
0/7/00	75 885	45 445	11.876	17 438	0.827	52 114	4 685	-50 378
0/8/00	113.678	105 664	12 060	43 282	0.820	85 032	9.005	-25 551
0/0/00	75 701	101.004	12.300	67 126	0.054	30 362	7817	9 880
0/10/00	AQ 071	08 777	11.977	74 207	1 043	0 832	11 210	25 441
0/11/00	-3.710	90.272	10.122	78 163	1.045	0.632	13.028	-10.636
0/17/00	7 607	71 212	0.122	70.103	1.044	0.000	10.020	×10.050 6.856
0/12/99	•7.097 0.076	121577	9.379	75.040	1.012	5 544	10.002	50 730
0/14/00	9.070 93.935	168,006	0.713	97 044	0.767	12 751	0.286	-39.750
0/15/00	35.050	22 657	9.527	20 616	0.731	2 404	9.200	-2
2/1J/22 0/16/00	23.039	22.0J7 56 A95	9,074	00.015	0.577	0.004	7.231	54 901
9/10/99	-102.320	50.465	9.500	90.015	0.309	10 751	6 709	-140.440
7/1//77 0/10/00	-37.037	60.424	0.000	73,077	0.505	12.701	0.700	-26.110
9/18/99	2.827	08.020	7.003	73.971	0.372	21.099	7.041	-7.232
9/19/99 0/20/00	15.127	90.200	8.042	73.387	0.704	10.293	2 212	-10.900
9/20/99	-1.113	04.811	9,404	74.740	0.920	28.489 0 822	5.210 6.042	-47.380
9/21/99	50.500	43.332	9,313	70.700	1.144	0.832	10 225	07.741
9/22/99	-20.133	105 150	8.001	12.44U 66 191	1.294	0.000	12.333	-43.755
9123199 0/24/00	11.921	103.152	0.217	70,484	1.137	10,524	2 005	-10.727
9/24/99	18.809	/1.568	0.002	70.509	1.107	10.3.34	2 122	15.155
9/23/99 0/26/00	27.219	90.909	10.007	//. 340	1.140	09.023	3.13Z 4 695	-23.234
9/20/99	23.093	101.830	12.204	82.087	1.270	10,909	4.080	-7.550
9/2//99 0/00/00	24.981	110.268	12.048	84.201 00.000	1.606	4.99U	8.011	-3.6/1
9/28/99	35.177	140.945	9.794	88.209	1.605	0.000	12.086	-7.078
9/29/99	41.470	98.524	9.271	94.328	1.481	0.000	10.506	46.299
9/30/99	-24.851	86.004	9.400	96.383	1.452	0.000	12.141	-3.783
Date	Change in	Inflow	Seepage	Outflow	Seepage	Rain	ET	Remainders
----------	--------------------	----------	---------	---------	---------------	---------	----------------	------------
Dan	Storage	Spillway	Pump	Pump	L-7a			
		G302 S	G250S	G251				
	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m
10/1/99	-35.983	77.392	9.266	92.133	1.430	0.000	8.870	-13.801
10/2/99	-47.881	72.041	9.831	84.561	1.398	0.000	12.502	-24.257
10/3/99	-16.402	70.502	9.378	80.441	1.394	0.000	5.738	-2.119
10/4/99	-13.708	75.415	8.559	79.004	1. 465	54.331	5.211	-60.704
10/5/99	33.688	117.973	9.109	80.164	1. 704	0.000	7.290	1.465
10/6/99	37.111	87.852	8.456	82.701	1.745	0.000	5.738	35.954
10/7/99	-61.570	0.000	8.982	84.020	2.080	16.909	6.764	10.225
10/8/99	-63.209	59,396	10.751	70.644	2.126	26.057	7.817	-72.327
10/9/99	101.119	150.920	12.552	74.064	2.116	40.748	9.369	-9.233
10/10/99	46.927	139.171	10.095	81.818	2.161	0.000	13.001	0.413
10/11/99	46.641	136.730	9.021	88.290	2.053	2.218	11.44 8	5.379
10/12/99	27,581	50.554	8.674	93.459	2.098	2.218	8.316	74.488
10/13/99	-97.855	0.000	7.519	92.415	2.447	0.000	10.922	3.035
10/14/99	-100.612	0.000	8.688	74.096	2.758	59.044	2.606	-85.712
10/15/99	48.351	0.000	6.839	45.467	3.595	415.523	1.053	-324.247
10/16/99	320.017	0.000	0.000	0.000	4.824	6.376	6.764	315.581
10/17/99	47.242	0.000	17.844	54.655	5.286	0.000	9.342	105.952
10/18/99	-27.584	0.000	23,491	91.945	5.805	0.000	10.922	69.477
10/19/99	-86 866	0.000	15.816	88.431	6.159	0.000	10.922	6.329
10/20/99	-85 974	0.000	11.064	80.083	6.347	74.012	9.369	-76.881
10/21/99	-11 968	105 365	9.471	65.985	5.948	0.000	9,369	-47.926
10/22/99	57 292	169 200	7.888	64.987	5.176	0.000	7.789	-44.308
10/23/99	74 900	154 424	7.984	77.879	4,588	0.000	12.474	6.241
10/24/99	50 278	66 837	6.812	88.561	4.157	0.000	12.446	80.291
10/25/99	-79 022	0.000	7.678	90.717	4.212	0.000	10.367	17.851
10/26/99	-113 161	37.963	8.930	76.758	4.108	0.000	5.184	-73.290
10/27/99	-18 974	101 113	9.077	64.072	3.670	1.386	10.894	-50.177
10/28/99	9 4 8 1	97 460	9.846	65.628	3.213	0.000	9.841	-15.723
10/20/00	18 859	95 984	9.687	68.315	2.912	0.832	8.815	-3.740
10/20/00	8 705	78 784	9.033	70.257	2.747	0.000	9.342	6.773
10/31/00	10.759	72 868	11 201	71 126	2.711	154.123	8,288	-139.529
11/1/00	56 024	0.268	13 944	81 899	3.224	4.990	9.868	131.210
11/0/00	-67 041	58 540	11.003	69 964	3.786	14.137	6.764	-62.677
11/3/00	-6.029	93 379	11.008	66 636	3.517	0.000	11.947	-24.341
11/4/00	-28 590	81 720	15.620	67.424	3.149	0.000	9.314	-36.722
11/5/00	-20.000	0.000	15 776	66.210	3.058	0.000	9.314	2.441
11/6/00	-69.026	0.000	14 866	57.823	3.058	0.000	7.762	-6.549
11/0/33	-60.603	0.000	13 902	50.016	3.065	0.000	8.815	-4.837
11/2/00	-55 754	0.000	13 440	44 552	3,102	0.000	9.314	-4.990
11/0/22	+C1.CC- AA0 SA.	0.000	13 535	36.850	3.168	0.000	9.841	-20.444
11/2/22	_40.500	0.000	13.036	33.067	3.192	0.000	9.314	-1.506
11/11/00	-40-034	0.000	13.020	28 759	3 163	0.000	7.263	-5.001
11/11/99	-27-027 2 222	52 A27	12.022	26.011	2 921	0.000	10.894	-27.422
11/12/99	0.343	0 000	12.955	26.011	2.921	0.000	9.314	32.154
11/17/00	-0.231 20.251	0.000	12 751	25.001	2.940	0.000	9.841	4.080
11/14/77	-20,202	72 543	10.201	23 643	2.676	0.000	10.367	-26.284
11/13/77	よう・ライン	10.040	1	40.040	2.010			

Date	Change in Storage	Inflow Spillway	Seepage Pump	Outflow Pump	Seepage L-7a	Rain	ET	Remainders
	ha-m	G302_S ha-m	G250S ha-m	G251 ba-m	ba-m	ha-m	ha-m	ba-m
11/16/99	40 764	66 400	14 370	24 805	2 564	0.000	0 841	6 527
11/17/99	16 360	61 987	14.572	30.024	2.504	0.000	6 209	.11803
11/18/99	20.694	70 433	15 358	35 316	2 303	0.000	7 235	-9.497
11/19/99	16 712	56 154	15.069	39 512	2 212	0.000	7 235	5 092
11/20/99	2 450	50.605	14 996	41 665	2171	0.000	7 235	-1 426
11/21/99	19 740	55 805	14.935	43 789	2.171	0.000	6 209	11 822
11/22/99	11.666	63 015	15 953	44 648	2.052	0.000	5 184	-3 570
11/23/99	6.076	53 456	15,000	46 572	2.052	0.000	3 631	0.705
11/24/99	-7.956	50,118	14 162	46 710	2.085	0.000	3 105	-5 344
11/25/99	-31 668	0.000	14 531	46 103	2.172	4.990	3 631	10 905
11/26/99	-23 492	50.965	14 485	41 636	2 175	0.000	4 657	-30 339
11/27/99	3 648	61 530	14 668	40.836	2 1 2 2	0.000	7 762	-11 407
11/28/99	7 756	60.938	14 325	42 827	2104	0.000	7 263	-5 195
11/29/99	1 320	58 807	14 776	44 491	2.055	0.000	6 736	-8 315
11/30/99	4.679	59.475	14.379	46 740	1978	0.000	6.736	-3.298
12/1/99	-4 169	59 695	13 797	48 834	1927	0.000	7 762	-9 195
12/2/99	-15 654	50 194	13.090	47.956	1 898	0.000	8 261	-11 530
12/3/99	-15 381	56 360	13,007	46 434	1901	0.000	5 683	-21 526
12/4/99	9 059	67 422	13.462	46 977	1 855	0.000	4 130	-21.220
12/5/99	1 866	50 762	13.281	48 315	1 873	3 604	3 604	.7 454
12/6/99	-3 706	55 044	13.201	53 003	1 884	0.000	5 683	-1.948
12/7/99	-5.700	34 354	13,440	48 418	1 878	0.000	6 209	12 561
12/8/99	-1.413	58 056	13 261	47.001	1.808	0.000	6736	_8 430
12/0/99	5 950	61 000	13 330	47.001	1.308	0.000	6736	-2.439
17/10/99	14.066	59.866	14 707	48 149	1.774	0.832	3 631	3 405
12/11/99	4 4 1 1	55 531	18 208	48 856	1.744	0.000	5 683	1.675
12/12/00	7.711	54 051	21.671	40 835	1.744	5 544	3.631	-6 205
12/13/99	-4 716	50 539	21.071	49.632	1.751	2.218	6 736	-2.205
12/14/99	-7.710	53 781	21.685	50 106	1.707	4 158	3 105	-2.070
12/15/99	6.003	56 404	21.000	52 377	1.710	0.832	3 631	3 136
12/16/99	-1 200	48 773	20.638	53.485	1.040	0.000	3 631	3 452
12/17/99	-10 386	47 611	20.000	52 727	1.595	0.000	6 209	-10 698
12/17/22	-0.523	51 799	20.802	50 703	1 741	2.218	5 683	0.105
12/10/99	-6.511	44 974	21.394	49.519	1.741	0.000	8 788	4 608
12/20/99	-10.966	34 479	21 379	49 903	1 647	1 386	5 184	609 6
12/20/22	-3.104	50 788	20.941	49,909	1.658	3 604	3 631	-15 783
12/21/99	10 024	63.605	20.941	48.738	1.658	0.832	7 763	1 032
12/22/99	13.510	62.805	21.516	53 461	1.600	11 020	5 184	-4 170
12/23/99	-5 324	47 303	21.140	56 610	1.553	0.000	7 767	10 113
12/25/00	-38 162	8353	20.866	52 776	1.555	0.000	9.813	14 533
12/26/99	-28 973	31 396	20.800	47 378	1.540	0.000	8 760	_5 795
12/27/99	-0.606	67 110	10 356	56 238	1 538	0.000	9.286	1 270
12/28/99	16 152	52.110	12.000	45 003	1 575	11 920	3 077	_1 874
12/29/99	-7 300	56 338	8 258	46 600	1.575	0.832	0.258	-1.024
12/30/00	-2.570	55 271	0.200	46 947	1 488	0.000	9.258	-3.165
12/31/99	-3 433	53 764	8 231	47 026	1 472	0.000	9 258	-2 385

Date	Change in	Inflow	Seenage	Outflow	Seepage	Rain	ЕT	Remainders
	Storage	Spillway	Pump	Pump	L-7a			
	2	G302_S	G250S	G251				
	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m
1/1/00	-2.256	54.349	8.683	47.036	1.439	0.000	7.928	-3.080
1/2/00	-8.655	52.355	8.522	47.268	1.445	0.000	7.540	-7.647
1/3/00	-2.933	58.648	9.168	46.505	1.430	0.000	7.429	-9.076
1/4/00	-28.569	0.000	13.795	45.668	1.482	0.000	8.011	23.629
1/5/00	-51.867	57.659	18.837	42.101	1.411	0.832	8.233	-61.435
1/6/00	22.629	53.077	25.057	40.623	1.376	2.772	9.064	15.091
1/7/00	-2.717	36.806	27.063	43.319	1.372	2.218	6.015	6.222
1/8/00	0.474	47.515	27.335	44.156	1.327	0.832	8.233	3.189
1/9/00	-8.904	37.119	26.789	43.008	1.326	0.000	7.983	3.643
1/10/00	0.406	50.214	26.647	41.379	1.315	0.000	8.787	-0.958
1/11/00	13.698	53.275	26.383	41.853	1.245	0.832	5.599	5.800
1/12/00	3.582	51.119	26.422	43.997	1.215	0.832	9.979	4.392
1/13/00	-2.513	46.297	26.390	44.234	1.201	0.000	9.563	3.787
1/14/00	1.085	50.052	26.368	46.996	1.069	0.000	9.148	6.108
1/15/00	-5.666	55.780	26.072	48.800	1.113	0.000	5.100	-8.660
1/16/00	1.374	53.448	26.031	46.084	1.125	0.000	6.182	-0.934
1/17/00	3.235	49.886	26.165	46.052	1.100	0.000	9.841	8.141
1/18/00	15.180	· 112.492	25.336	46.189	1.037	0.832	9.702	-43.291
1/19/00	46,720	117.545	25.409	49.803	0.984	0.832	6.653	-16.185
1/20/00	35,389	107.553	24.863	56.115	0.936	0.832	8.261	-9.554
1/21/00	62.751	136.916	25.588	63.820	0.885	0.000	10.312	-0.918
1/22/00	18.336	98.722	25.810	70.084	0.875	0.000	9.841	-1.338
1/23/00	-16.660	84.228	26.755	67.343	0.892	0.000	9.342	-25.094
1/24/00	21.956	78,508	24.100	68.055	0.892	27.443	3.964	-12.868
1/25/00	-3.680	59.785	23.178	63.487	1.054	0.000	6.791	5.760
1/26/00	-38.207	52.590	27.738	56.773	1.057	0.000	10.866	-24.214
1/27/00	-16.082	91.906	28.340	49.524	1.081	0.000	10.894	-48.652
1/28/00	49.815	138.092	28.284	49.093	1.048	13.306	7.457	-46.081
1/29/00	51.897	116.138	29.583	54.914	1.009	0.832	7.623	-3.545
1/30/00	26.055	99.131	29.510	58.914	1.006	0.832	9.175	-6.824
1/31/00	30.588	92,968	32.402	61.141	0.999	0.000	7.124	4.886
2/1/00	23.835	89 214	31.937	61.552	0.982	0.000	7.179	2.370
2/2/00	-8.023	46.916	32.458	63.864	0.979	0.000	3.770	11.717
2/3/00	-49.640	0.000	31.871	61.591	1.042	0.000	5.766	16.675
2/4/00	-56.547	0.000	32.382	51.846	1.097	0.000	8,399	2.601
2/5/00	-55 667	0.000	32.032	45.543	1.128	0.000	11.504	0.252
2/6/00	-65 579	0.000	32.084	40.909	1.088	0.000	8.926	-16.832
2/7/00	-42 473	0.000	32.091	38.871	1.081	0.000	7.789	3.107
2/8/00	-28.672	0.000	32.164	33.982	t.190	35.204	2.412	-28.673
2/9/00	82.507	117.337	31.511	30.303	1.067	17.741	11.448	-11.887
2/10/00	102.593	144 625	31.235	41.616	0.993	0.000	11.753	10.345
2/11/00	76 502	23 528	31-350	56 509	0.976	0.832	11,393	119.070
2/12/00	73 355	0.000	31 717	57 796	1 02.1	0.000	9,674	-6.906
2/13/00	-53 271	0.000	31 834	40 340	1 069	0.000	9,342	4,343
2/14/00	-58 157	0.000	31 961	40 726	1 1 10	0.000	10.534	-8.017
2/15/00	-40.038	0.000	32.103	39.412	1.095	0.000	11.975	10.254

Date	Change in Storage	Inflow Spillway	Seepage Pump	Outflow Pump	Seepage L-7a	Rain	ET	Remainders
		G302_S	G250S	G251				
	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m
2/16/00	-36.810	0.000	32.059	34.897	1.098	0.000	11.836	8.826
2/17/00	-34.708	0.000	32.081	32.999	1.125	0.000	12.252	9.418
2/18/00	-44.480	0.000	32.116	32.580	1.157	0.000	10.035	-3.022
2/19/00	-33.425	0.000	32.155	24.306	1.136	0.000	9.425	-0.831
2/20/00	-33.036	0.000	32.238	26.618	1.084	0.000	10.866	3.364
2/21/00	-27.651	0.000	32.270	24.225	1.016	0.000	12.613	8.170
2/22/00	-34.084	0.000	32.226	21.751	1.017	0.000	9.979	-3.371
2/23/00	-31.778	0.000	32.172	20.954	1.029	0.000	9.397	-2.457
2/24/00	-23.667	0.000	31. 69 7	19.065	1.027	1.386	10.644	3.629
2/25/00	-20.020	0.000	30.799	18.734	1.010	1.386	9.092	5.411
2/26/00	-17.154	0.000	30.919	16.687	0.999	0.000	8.898	7.432
2/27/00	-16.519	0.000	30.836	16.701	1.006	0.000	9.342	8.518
2/28/00	-21.629	0.000	30.173	16.679	0.952	0.000	9,619	3.717
2/29/00	5.333	0.000	29.451	5,789	0.952	0.000	11.836	22.006
3/1/00	26.325	64.872	28.338	0.000	0.835	0.000	12.030	-27.352
3/2/00	51.309	0.000	22.314	0.000	0.875	0.000	10.173	60.607
3/3/00	4,798	35,213	17.702	0.000	0.793	0.000	8.371	-22.836
3/4/00	21.358	28.247	16.320	0.000	0.731	0.000	9.924	2.304
3/5/00	21.689	31.382	16.322	0.000	0.660	0.000	12.668	2.316
3/6/00	24.532	46.108	16.312	0.000	0.601	0.000	9.813	-12.365
3/7/00	36 558	47 400	16 307	0,000	0 574	0.000	9.619	-1.797
3/8/00	39.650	53 622	16 310	0,000	0.551	0.000	10 700	-3 874
3/0/00	60.079	55 083	16310	0.000	0.568	0.000	13 444	17 873
3/10/00	35 108	0.000	16312	0.000	0.506	0.000	11047	46 449
3/11/00	14.003	0.000	17 374	0.000	0.500	37 422	7 767	-16 150
3/12/00	22 470	0,000	17.974	0.000	0.551	0.000	10 506	32 /3/
3/12/00	22.473	54 712	17.019	20.484	0.551	0.000	13 278	25 201
2/17/00	-3.745	42.052	16.004	20.404	0.500	0.000	13.270	-25.201
2/15/00	-0.555	42.932	10.227	23.240	0.518	0.000	10.450	-10.382
2/16/00	126.174	115.655	20.251	21.142	0.511	0.000	10.450	-45.410
2/10/00	120.203 02 405	114.472	21.252	21.104	0.331	0.000	12.001	44.090 20 206
2/1//00	00.403	105.055	21.222	32.803	0.427	6 2776	5.001	20.200
2/10/00	90.217	00.09Z	31.900 31.660	20.199 67.092	0.582	0.270	2,403	04.371
3/19/00	112.342	77.933	21.008	57.984 68.480	0.393	204.290	2.024	-110.2/4
3/20/00	200.247	204.171	31.337	03.439	0.856	0.832	12.337	Q8.4V2
3/21/00	1/4.05/	227.855	30.224	94.245	0.949	0.832	14.775	53.441
3/22/00	105.787	155.730	10.491	102.429	0.722	0.832	14.054	04.981
3/23/00	-28,180	3.283	19.429	105.270	0.676	0.832	13.389	85.087
3/24/00	-121.013	4.338	28.207	104.536	0.719	0.832	10.312	-12.004
3/25/00	-123,406	4.744	30.290	96.405	0.780	1.380	13.888	-20.024
3/26/00	-102.810	4.707	30.618	84.666	0.817	0.000	10.389	-13.080
3/27/00	-83.634	13.545	30.508	70.468	0.849	2.218	7.983	-21.794
3/28/00	- /0.639	2.447	29.745	08.403	0.888	3.604	14.553	-0.621
3/29/00	-83.492	25.712	30.594	64.116	0.946	2.218	12.973	-35.280
3/30/00	18.151	111.435	31.634	55.951	0.913	0.000	13.389	-24.858
3/31/00	32.961	4.859	32.069	60.664	0.921	0.000	12.197	100.041
4/1/00	-97.728	0.000	32.341	58.374	0.970	0.000	12.446	-27.878

.

Date	Change in	Inflow	Seepage	Outflow	Seepage	Rain	ET	Remainders
	Storage	Spillway	Pump	Pump	L-7a			
	• .	G302_S	G250S	G251	L	k	b	b
	ha-m	ba-m	na-m	na-m	na-m	na-m	10.045	12 260
4/2/00	-77.429	0.000	32.470	48.144	1.022	0.000	12.945	-17.362
4/3/00	-33.279	0.000	32.541	13.029	1.048	0.000	14.498	-6.801
4/4/00	16.894	0.000	32.465	0.000	0.978	-0.000	12.945	28.861
4/5/00	-42.786	0.000	32.409	14.693	0.886	0.000	10.577	-12.403
4/6/00	-17.831	33.312	28.521	17.484	0.914	0.000	13.472	-21.100
4/7/00	33.707	51.838	16.378	17.394	0.908	0.000	14.498	12.852
4/8/00	-6.349	0.000	16.364	17.369	0.931	0.000	13.472	23.561
4/9/00	-25.682	0.000	16.339	13.009	0.848	0.000	16.577	3.055
4/10/00	-7.413	0.991	16.288	0.000	0.872	0.000	14.498	5.222
4/11/00	-2.828	0.000	16.234	0.000	0.872	0.000	13.999	10.299
4/12/00	14.937	0.000	16.209	0.000	0.862	23.285	6.736	-2.474
4/13/00	56.759	111.511	15.872	27.929	0.866	42.966	4.657	-65.998
4/14/00	199.326	173.330	13.988	60.329	1.093	164.102	1.552	-77.318
4/15/00	279.739	225.477	26.620	82.114	1.230	30.215	8.815	113.746
4/16/00	199.614	85.684	29.113	87.556	0.740	31.046	13.999	183.699
4/17/00	-31.638	0.000	30.601	87.979	1.712	11.920	12.945	55.654
4/18/00	-88.464	39.265	30,185	88.047	1.718	0.000	15.024	-26.376
4/19/00	-26.102	92.598	27.848	90.323	1.407	0.000	16.577	-13.208
4/20/00	-51.970	1.099	28.206	90.749	1.234	0.000	12. 446	48.891
4/21/00	-117.631	0.000	30.263	95.368	1.248	0.000	14. 49 8	-9.013
4/22/00	-138.776	0.000	27.107	86.513	1.254	0.000	15.551	-37.966
4/23/00	-91.046	0.000	24.832	59.888	1.216	0.000	16.050	-16.324
4/24/00	-64.012	0.000	25.130	44.745	1.246	0.000	14. 49 8	-6.015
4/25/00	-55.267	0.509	26.845	32.974	1.114	2.772	11.920	-14.768
4/26/00	-1.859	103.415	25.402	32.994	0.859	0.000	16.577	-56.562
4/27/00	50.705	73.526	26.542	34.562	0.706	0.000	15.551	26.586
4/28/00	89.287	125.318	25.184	36.241	0.550	0.000	16.577	16.237
4/29/00	90.793	133.223	25.918	50.896	0.397	0.000	10.894	18.962
4/30/00	86.034	135.225	27.71 1	66.497	0.273	0.000	14. 498	31.530
5/1/00	51.618	129.478	27 .689	84.047	0.241	0.000	16.050	21.996
5/2/00	41.898	132.196	28.008	87.122	0.248	0.000	14.498	11.074
5/3/00	37.907	55.418	28.915	86.479	0.272	0.000	7.7 62	76.457
5/4/00	-105.965	20.572	31.372	9 9.116	0.413	0.000	15.551	-12.283
5/5/00	-75.137	45.423	32.465	81.356	0.373	0.000	16.577	-23.001
5/6/00	-43.471	51.281	31.560	71.946	0.384	0.000	14.498	-8.693
5/7/00	-55.886	44.068	31.607	59.421	0.355	0.000	14.498	-26.390
5/8/00	-21.201	58.821	31.604	55.567	0.359	0.000	8.815	-16.000
5/9/00	-11.897	53.896	31.589	53.143	0.403	0.000	16.050	2.996
5/10/00	-9.338	70.918	31.521	51.290	0.331	0.000	17.103	-12.194
5/11/00	-1.436	63.744	29.184	53.683	0.289	0.000	16.050	4.263
5/12/00	-9.305	60.666	31.602	53.289	0.342	0.000	17.103	0.079
5/13/00	-22.530	27.352	28.761	51.912	0.305	0.000	13.999	15.724
5/14/00	-69.968	0.000	31.910	49.930	0.307	0.000	16.577	-3.769
5/15/00	-54.567	0.000	30.723	40.513	0.300	13.306	15.024	-12.636
5/16/00	-31 233	0.000	23,726	37.420	0.270	0.000	16.050	21.966
5/17/00	-41.485	0.000	18.321	52.440	0.254	0.000	10.894	21.595

.

STA-1W Water Balance terms with calculated remainders

•

Date	Change in Storage	Inflow Spillway C302 S	Seepage Pump C2508	Outflow Pump C251	Seepage L-7a	Rain	ЕТ	Remainders
	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m	ha-m
5/18/00	-28.888	0.000	16.349	27.286	0.236	0.000	15.551	13.713
5/19/00	-8.300	99.562	15.965	20.496	0.190	0.000	14.498	-73.058
5/20/00	90.515	107.430	15.561	25,872	0.191	0.000	17.602	26.368
5/21/00	8.734	16.855	13.278	36.087	0.176	0.000	17.602	45.391
5/22/00	-40.661	0.000	14.242	34.092	0.134	0.000	15.024	8.322
5/23/00	-28.326	0.000	16.031	27.71 9	0.097	26.057	13.472	-13.289
5/24/00	-18.601	0.000	16.028	26.376	0.071	16.078	13.999	5.625
5/25/00	-20.158	0.000	12.087	20.222	0.040	7.762	16.050	8.312
5/26/00	-23.813	0.000	11.338	20.469	0.012	0.000	16.050	12.695
5/27/00	-38.708	0.000	15.683	17.396	0.000	0.000	11.920	-9.392
5/28/00	-37.852	0.000	12.082	17.345	0.000	0.000	15.551	-4.956
5/29/00	-32.109	0.000	13.401	11.800	0.000	0.000	16.577	-3.732
5/30/00	-29.819	0.000	31.034	46.629	0.000	0.000	13.472	30.282
5/31/00	-19.256	0.000	18.010	5.752	0.000	0.000	15.024	1.520
6/1/00	-15.036	0.000	4.879	0.000	0.000	0.000	15.551	0.515
6/2/00	-13.963	0.000	18.013	0.000	0.000	0.000	16.577	2.614
6/3/00	-7.281	0.000	12.708	0.000	0.000	0.000	16.050	8.769
6/4/00	-7.636	0.000	14.959	0.000	0.000	0.000	12.945	5.309
6/5/00	8.248	34.763	16.926	0.000	0.000	0.000	17.103	-9.412
6/6/00	-5.939	41.181	13.481	19.515	0.000	0.000	14.498	-13.107
6/7/00	-8.331	32.098	13.521	12.537	0.000	0.000	13.472	-14.421
6/8/00	27.170	46.118	8.625	9.256	0.000	11.365	5.710	-15.347
6/9/00	29.647	46.502	12.378	7.401	0.000	0.000	12.945	3.491
6/10/00	12. 465	0.245	18.013	5,838	0.000	0.832	14.498	31.724
6/11/00	31.850	0.000	17.633	10.386	0.000	56.272	8.288	-5.747
6/12/00	21.540	0.000	15.128	6.616	0.000	0.000	16.050	44.205
6/13/00	0.344	0.000	18.010	6.481	0.000	0.000	12.446	19.272
6/14/00	-18.637	0.000	11.783	5.454	0.000	0.000	13.999	0.815
6/15/00	-31.598	0.000	18.013	1.515	0.000	0.000	15.024	-15.059
6/16/00	-28.342	0.000	11.820	2.860	0.000	0.000	17.602	-7.880
6/17/00	-18.888	0.000	12.603	4.314	0.000	2.218	16.050	-0.743
6/18/00	-21.349	0.000	14.042	0.000	0.000	0.000	15.024	-6.325
6/19/00	-20.127	0.000	12.985	5.713	0.000	4.158	10.894	-7.678
6/20/00	11.440	57.363	17.352	0.000	0.000	0.000	16.050	-29.874
6/21/00	58.407	54.427	10.337	1.806	0.000	0.000	10.367	16.153
6/22/00	38.430	55.391	12.109	7.732	0.000	0.000	13.472	4.242
6/23/00	29.876	48.856	14.759	6.978	0.000	0.000	15.551	3.549
6/24/00	10.260	0.000	10.244	11.989	0.000	0.000	11.393	33.642
6/25/00	-18.040	0.000	12.493	8.145	0.000	1.386	5.184	-6.097
6/26/00	14.568	99.547	17.227	5.728	0.000	0.000	12.446	-66.805
6/27/00	90.633	78.400	19.478	10.797	0.000	5.544	6.209	23.695
6/28/00	32.826	0.000	24.032	13.195	0.000	0.000	10.894	56.915
6/29/00	-21.145	0.000	26.106	17.372	0.000	1.386	8.288	3.129
6/30/00	-16.502	0.000	27.134	10.457	0.000	16.909	12.945	-10.008