

Miami-Dade Transit Metrorail Operations Plan

Dadeland South to Palmetto Station (Tail Track to Yard Limit)



Roosevelt Bradley
Director

Revision 7

February 2003

Includes: Appendix A: Operating Plan, Inclusion of Palmetto Station
Appendix B: Metrorail Train Verification Testing Procedure
Addendum

**MIAMI-DADE TRANSIT
METRORAIL OPERATION PLAN
DADELAND SOUTH TO PALMETTO STATION
(TAIL TRACK TO YARD LIMIT)
Revision 7
February 2003**

DOCUMENT: **Dadeland South to Palmetto Station**
Appendix A: Operating Plan, Inclusion of Palmetto Station
Appendix B: Metrorail Train Verification Testing Procedure
Addendum

DATE:

REVISION:

SUBMITTED BY:

APPROVAL:

Gregory N. Robinson
General Superintendent
Rail Transportation

Aurelio Rodriguez
Assistant Director
Engineering and Construction

Hannie L. Woodson
General Superintendent
Rail/Mover Maintenance

Ruby Hemingway-Adams
Assistant Director
Customer Development

Victor Bravo
General Superintendent
Track and Guideway

Hugh Chen
Chief
Field Test Eng. and Systems Maintenance

Bonnie L. Todd
Chief
Safety and Security

Joseph Mesa
Manager
Transit Systems Section

**Metrorail Operations Plan
Dadeland South to Palmetto Station
Table of Contents**

	<u>Page</u>
INTRODUCTION	
PURPOSE	1
SCOPE	1 - 2
REFERENCE DOCUMENTATION	3
LIST OF ACRYNONYMS	4
SECTION 1 – SYSTEM CONFIGURATION	5 – 23
1.0 Physical Description	5 – 6
Mainline	
William Lehman Center Yard Facilities	
Stephen P. Clark Center	
Central Control Facility	
Metrorail Transit System	
Metrorail Passenger Station	
1.1 Central Control Facility Summary	7 – 10
Central Control	
Central Control Facility Equipment	
Train Control Console	
Supervisory Communication and Data Acquisition (SCADA)	
Station Operation Console	
Building Alarm Panel	
Other Equipment at Central Control Facility	
1.2 Train Control System Summary	10 – 12
Automatic Train Control	
Automatic Train Operation	
Automatic Train Protection	
Automatic Train Supervision	
1.3 Traction Power Summary	12 – 15
1.4 Communication Summary	16 – 18
Radio System Overview	
1.5 Facilities Maintenance Summary	18

**Metrorail Operations Plan
Dadeland South to Palmetto Station
Table of Contents**

		<u>Page</u>
1.6	Metrorail Train Familiarization Summary Car Characteristics Train Description	19 – 20
1.7	Train Modes of Operation ATO Mode Manual Mode Yard Mode Yard Mode/ATP By-Pass	20 - 22
SECTION 2 – SYSTEM OPERATIONS & SERVICE CONFIGURATION		24 – 43
2.0	Operating Hours and Service Levels Mainline Operations Track Allocation Passenger Service Preparation a. Sweep Train b. Station Opening Service Levels Vehicle Requirements	24 – 29
2.1	Daily Operation Peak Service Off Peak Service Failure Management Station Stops Speed and Travel Times Vehicle Storage	29 – 34
2.2	Traction Power/Supervisory Control and Data Acquisition (SCADA) Console System Overview Emergency Trip Station (ETS) Activation of Emergency Trip Station (ETS) Train Control Console/Panel Interlocking Operation and Control Train Control Maintenance Train Status Board Terminal Operations Predeparture Test	34 – 40

**Metrorail Operations Plan
Dadeland South to Palmetto Station
Table of Contents**

	<u>Page</u>
2.3 Summary of Duties of Operating Personnel	41 – 43
Rail Traffic Controller	
Mainline Vehicle Maintenance Technicians	
Personnel on Guideway for Maintenance/Inspector or Other Purposes	
Rail Yard Master at Palmetto Yard	
Train Operator	
Rail Supervisor	
Security	

TABLES

Table 1-1: MDT Metrorail Passenger Stations	6
Table 1-2: Metrorail System 9 Radio Channel	18
Table 2-1: Vehicle Requirements	27
Table 2-2: Weekday and Weekend Vehicle Requirements	28
Table 2-3: Weekday Service	30
Table 2-4: Estimated Station-to-Station Travel Times	32
Table 2-5: Vehicle Storage Location	33
Table 2-6: Staff Locations	38

APPENDICES

Appendix A: Operating Plan, Inclusion of Palmetto Station	
Appendix B: Metrorail Train Verification Testing Procedure	
Addendum	